


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING				FORM 3 AMENDED REPORT <input type="checkbox"/>		
APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER Greater Monument Bute L-22-8-17		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT MONUMENT BUTTE		
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)		
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY				7. OPERATOR PHONE 435 646-4825		
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052				9. OPERATOR E-MAIL mcrozier@newfield.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-77233		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Brad and Joann Nelson				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') PO Box 638, Roosevelt, UT 84066				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>		19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2007 FNL 2000 FEL	SWNE	22	8.0 S	17.0 E	S
Top of Uppermost Producing Zone	2340 FNL 1368 FEL	SWNE	22	8.0 S	17.0 E	S
At Total Depth	2547 FNL 1004 FEL	SENE	22	8.0 S	17.0 E	S
21. COUNTY DUCHESNE		22. DISTANCE TO NEAREST LEASE LINE (Feet) 1004		23. NUMBER OF ACRES IN DRILLING UNIT 20		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 933		26. PROPOSED DEPTH MD: 6735 TVD: 6735		
27. ELEVATION - GROUND LEVEL 5124		28. BOND NUMBER WYB000493		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478		
ATTACHMENTS						
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES						
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER			<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN			
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)			<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER			
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)			<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP			
NAME Mandie Crozier		TITLE Regulatory Tech		PHONE 435 646-4825		
SIGNATURE		DATE 11/03/2010		EMAIL mcrozier@newfield.com		
API NUMBER ASSIGNED 43013504640000		APPROVAL  Permit Manager				

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	5.5	0	6735		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	6735	15.5			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	8.625	0	350		
Pipe	Grade	Length	Weight			
	Grade J-55 ST&C	350	24.0			

NEWFIELD PRODUCTION COMPANY
GREATER MONUMENT BUTTE L-22-8-17
AT SURFACE: SW/NE SECTION 22, T8S, R17E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1835'
Green River	1835'
Wasatch	6575'
Proposed TD	6735'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1835' – 6575'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sample Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM****a. Casing Design: Greater Monument Butte L-22-8-17**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	350'	24.0	J-55	STC	2,950 15.02	1,370 12.30	244,000 29.05
Prod casing 5-1/2"	0'	6,735'	15.5	J-55	LTC	4,810 2.24	4,040 1.89	217,000 2.08

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: Greater Monument Butte L-22-8-17

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	350'	Class G w/ 2% CaCl	161 188	30%	15.8	1.17
Prod casing Lead	4,735'	Prem Lite II w/ 10% gel + 3% KCl	327 1067	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 350 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 350 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 350' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2011, and take approximately seven (7) days from spud to rig release.

T8S, R17E, S.L.B.&M.

N89°31'W - 79.96 (G.L.O.)

S89°21'03"W - 5288.46' (Meas.)



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are base on LOCATION: an N.G.S. OPUS Correction.
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'

L-22-8-17
(Surface Location) NAD 83
LATITUDE = 40° 06' 18.71"
LONGITUDE = 109° 59' 24.97"

NEWFIELD EXPLORATION COMPANY


WELL LOCATION, L-22-8-17, LOCATED AS SHOWN IN THE SW 1/4 NE 1/4 OF SECTION 22, T8S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, L-22-8-17, LOCATED AS SHOWN IN THE SE 1/4 NE 1/4 OF SECTION 22, T8S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**


1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 08-13-10	SURVEYED BY: D.G.
DATE DRAWN: 09-30-10	DRAWN BY: M.W.
REVISED:	SCALE: 1" = 1000'



Legend

○—○ Existing Road

P: (435) 781-2501
F: (435) 781-2518



Tri State
Land Survey

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

DRAWN BY: C.H.M

DATE: 09-21-2010

SCALE: 1:100,000

**NEWFIELD EXPLORATION COMPANY**

I-22-8-17 (Proposed Well)

L-22-8-17 (Proposed Well)

32-22-8-17 (Existing Well)


SEC. 22, T8S, R17E, S.L.B.&M. Duchsene County, UT.

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

○ Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


I-22-8-17 (Proposed Well)
L-22-8-17 (Proposed Well)
32-22-8-17 (Existing Well)
SEC. 22, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: C.H.M.
DATE: 09-21-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

SHEET
B

Proposed Pipeline Map



Legend

- Existing Road
- Proposed Flowline

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


I-22-8-17 (Proposed Well)
L-22-8-17 (Proposed Well)
32-22-8-17 (Existing Well)
SEC. 22, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: C.H.M.
DATE: 09-21-2010
SCALE: 1" = 2,000'



TOPOGRAPHIC MAP

SHEET
C

Exhibit "B" Map



Legend

-  1 Mile Radius
-  Proposed Location



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

N



NEWFIELD EXPLORATION COMPANY

I-22-8-17 (Proposed Well)
L-22-8-17 (Proposed Well)
32-22-8-17 (Existing Well)
SEC. 22, T8S, R17E, S.L.B.&M. Duchsene County, UT.

DRAWN BY: C.H.M.
DATE: 09-21-2010
SCALE: 1" = 2,000'

TOPOGRAPHIC MAP

SHEET

D

NEWFIELD



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 22 T8S, R17E
L-22-8-17**

Wellbore #1

Plan: Design #1

Standard Planning Report

27 September, 2010





PayZone Directional Services, LLC.

Planning Report



Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well L-22-8-17
Company:	NEWFIELD EXPLORATION	TVD Reference:	L-22-8-17 @ 5136.0ft (Original Well Elev)
Project:	USGS Myton SW (UT)	MD Reference:	L-22-8-17 @ 5136.0ft (Original Well Elev)
Site:	SECTION 22 T8S, R17E	North Reference:	True
Well:	L-22-8-17	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 22 T8S, R17E, SEC 22 T8S, R17E				
Site Position:		Northing:	7,208,900.00 ft	Latitude:	40° 6' 1.964 N
From:	Lat/Long	Easting:	2,062,000.00 ft	Longitude:	109° 59' 34.084 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence:	0.97 °

Well	L-22-8-17, SHL LAT: 40° 06' 18.71, LONG: -109° 59' 24.97					
Well Position	+N/-S	1,694.4 ft	Northing:	7,210,606.09 ft	Latitude:	40° 6' 18.710 N
	+E/-W	708.1 ft	Easting:	2,062,679.44 ft	Longitude:	109° 59' 24.970 W
Position Uncertainty		0.0 ft	Wellhead Elevation:	5,136.0 ft	Ground Level:	5,124.0 ft

Wellbore Wellbore #1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/09/27	11.38	65.88	52,387

Design Design #1

Audit Notes:

Version: Phase: PROTOTYPE Tie On Depth: 0.0

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	5,400.0	0.0	0.0	117.76

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,357.7	11.37	117.76	1,352.8	-34.9	66.3	1.50	1.50	0.00	117.76	
5,485.9	11.37	117.76	5,400.0	-413.8	786.2	0.00	0.00	0.00	0.00	L-22-8-17 TGT
6,735.4	11.37	117.76	6,625.0	-528.5	1,004.1	0.00	0.00	0.00	0.00	



PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 22 T8S, R17E
Well: L-22-8-17
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well L-22-8-17
TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	117.76	700.0	-0.6	1.2	1.3	1.50	1.50	0.00
800.0	3.00	117.76	799.9	-2.4	4.6	5.2	1.50	1.50	0.00
900.0	4.50	117.76	899.7	-5.5	10.4	11.8	1.50	1.50	0.00
1,000.0	6.00	117.76	999.3	-9.7	18.5	20.9	1.50	1.50	0.00
1,100.0	7.50	117.76	1,098.6	-15.2	28.9	32.7	1.50	1.50	0.00
1,200.0	9.00	117.76	1,197.5	-21.9	41.6	47.0	1.50	1.50	0.00
1,300.0	10.50	117.76	1,296.1	-29.8	56.6	64.0	1.50	1.50	0.00
1,357.7	11.37	117.76	1,352.8	-34.9	66.3	74.9	1.50	1.50	0.00
1,400.0	11.37	117.76	1,394.2	-38.8	73.7	83.2	0.00	0.00	0.00
1,500.0	11.37	117.76	1,492.3	-47.9	91.1	102.9	0.00	0.00	0.00
1,600.0	11.37	117.76	1,590.3	-57.1	108.5	122.7	0.00	0.00	0.00
1,700.0	11.37	117.76	1,688.3	-66.3	126.0	142.4	0.00	0.00	0.00
1,800.0	11.37	117.76	1,786.4	-75.5	143.4	162.1	0.00	0.00	0.00
1,900.0	11.37	117.76	1,884.4	-84.7	160.9	181.8	0.00	0.00	0.00
2,000.0	11.37	117.76	1,982.4	-93.8	178.3	201.5	0.00	0.00	0.00
2,100.0	11.37	117.76	2,080.5	-103.0	195.7	221.2	0.00	0.00	0.00
2,200.0	11.37	117.76	2,178.5	-112.2	213.2	240.9	0.00	0.00	0.00
2,300.0	11.37	117.76	2,276.6	-121.4	230.6	260.6	0.00	0.00	0.00
2,400.0	11.37	117.76	2,374.6	-130.6	248.1	280.3	0.00	0.00	0.00
2,500.0	11.37	117.76	2,472.6	-139.7	265.5	300.0	0.00	0.00	0.00
2,600.0	11.37	117.76	2,570.7	-148.9	282.9	319.7	0.00	0.00	0.00
2,700.0	11.37	117.76	2,668.7	-158.1	300.4	339.4	0.00	0.00	0.00
2,800.0	11.37	117.76	2,766.8	-167.3	317.8	359.1	0.00	0.00	0.00
2,900.0	11.37	117.76	2,864.8	-176.5	335.2	378.8	0.00	0.00	0.00
3,000.0	11.37	117.76	2,962.8	-185.6	352.7	398.6	0.00	0.00	0.00
3,100.0	11.37	117.76	3,060.9	-194.8	370.1	418.3	0.00	0.00	0.00
3,200.0	11.37	117.76	3,158.9	-204.0	387.6	438.0	0.00	0.00	0.00
3,300.0	11.37	117.76	3,257.0	-213.2	405.0	457.7	0.00	0.00	0.00
3,400.0	11.37	117.76	3,355.0	-222.4	422.4	477.4	0.00	0.00	0.00
3,500.0	11.37	117.76	3,453.0	-231.5	439.9	497.1	0.00	0.00	0.00
3,600.0	11.37	117.76	3,551.1	-240.7	457.3	516.8	0.00	0.00	0.00
3,700.0	11.37	117.76	3,649.1	-249.9	474.8	536.5	0.00	0.00	0.00
3,800.0	11.37	117.76	3,747.1	-259.1	492.2	556.2	0.00	0.00	0.00
3,900.0	11.37	117.76	3,845.2	-268.2	509.6	575.9	0.00	0.00	0.00
4,000.0	11.37	117.76	3,943.2	-277.4	527.1	595.6	0.00	0.00	0.00
4,100.0	11.37	117.76	4,041.3	-286.6	544.5	615.3	0.00	0.00	0.00
4,200.0	11.37	117.76	4,139.3	-295.8	562.0	635.0	0.00	0.00	0.00
4,300.0	11.37	117.76	4,237.3	-305.0	579.4	654.7	0.00	0.00	0.00
4,400.0	11.37	117.76	4,335.4	-314.1	596.8	674.5	0.00	0.00	0.00
4,500.0	11.37	117.76	4,433.4	-323.3	614.3	694.2	0.00	0.00	0.00
4,600.0	11.37	117.76	4,531.5	-332.5	631.7	713.9	0.00	0.00	0.00
4,700.0	11.37	117.76	4,629.5	-341.7	649.1	733.6	0.00	0.00	0.00
4,800.0	11.37	117.76	4,727.5	-350.9	666.6	753.3	0.00	0.00	0.00
4,900.0	11.37	117.76	4,825.6	-360.0	684.0	773.0	0.00	0.00	0.00
5,000.0	11.37	117.76	4,923.6	-369.2	701.5	792.7	0.00	0.00	0.00
5,100.0	11.37	117.76	5,021.7	-378.4	718.9	812.4	0.00	0.00	0.00
5,200.0	11.37	117.76	5,119.7	-387.6	736.3	832.1	0.00	0.00	0.00

NEWFIELD



PayZone Directional Services, LLC.

Planning Report



Database: EDM 2003.21 Single User Db
Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 22 T8S, R17E
Well: L-22-8-17
Wellbore: Wellbore #1
Design: Design #1

Local Co-ordinate Reference: Well L-22-8-17
TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	11.37	117.76	5,217.7	-396.8	753.8	851.8	0.00	0.00	0.00
5,400.0	11.37	117.76	5,315.8	-405.9	771.2	871.5	0.00	0.00	0.00
5,485.9	11.37	117.76	5,400.0	-413.8	786.2	888.5	0.00	0.00	0.00
L-22-8-17 TGT									
5,500.0	11.37	117.76	5,413.8	-415.1	788.7	891.2	0.00	0.00	0.00
5,600.0	11.37	117.76	5,511.8	-424.3	806.1	910.9	0.00	0.00	0.00
5,700.0	11.37	117.76	5,609.9	-433.5	823.5	930.6	0.00	0.00	0.00
5,800.0	11.37	117.76	5,707.9	-442.6	841.0	950.4	0.00	0.00	0.00
5,900.0	11.37	117.76	5,806.0	-451.8	858.4	970.1	0.00	0.00	0.00
6,000.0	11.37	117.76	5,904.0	-461.0	875.9	989.8	0.00	0.00	0.00
6,100.0	11.37	117.76	6,002.0	-470.2	893.3	1,009.5	0.00	0.00	0.00
6,200.0	11.37	117.76	6,100.1	-479.4	910.7	1,029.2	0.00	0.00	0.00
6,300.0	11.37	117.76	6,198.1	-488.5	928.2	1,048.9	0.00	0.00	0.00
6,400.0	11.37	117.76	6,296.2	-497.7	945.6	1,068.6	0.00	0.00	0.00
6,500.0	11.37	117.76	6,394.2	-506.9	963.0	1,088.3	0.00	0.00	0.00
6,600.0	11.37	117.76	6,492.2	-516.1	980.5	1,108.0	0.00	0.00	0.00
6,700.0	11.37	117.76	6,590.3	-525.3	997.9	1,127.7	0.00	0.00	0.00
6,735.4	11.37	117.76	6,625.0	-528.5	1,004.1	1,134.7	0.00	0.00	0.00

Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- hit/miss target									
- Shape									
L-22-8-17 TGT	0.00	0.00	5,400.0	-413.8	786.2	7,210,205.60	2,063,472.52	40° 6' 14.620 N	109° 59' 14.851 W
- plan hits target									
- Circle (radius 75.0)									





Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 11.38°

Magnetic Field
 Strength: 52387.2snT
 Dip Angle: 65.88°
 Date: 2010/09/27
 Model: IGRF2010

KOP @ 600'
 DOGLENG RATE 1.5 DEG/100
 TARGET RADIUS IS 75'



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
L-22-8-17 TGT	5400.0	-413.8	786.2	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1357.7	11.37	117.76	1352.8	-34.9	66.3	1.50	117.76	74.9	
4	5485.9	11.37	117.76	5400.0	-413.8	786.2	0.00	0.00	888.5	L-22-8-17 TGT
5	6735.4	11.37	117.76	6625.0	-528.5	1004.1	0.00	0.00	1134.7	



MEMORANDUM
of
EASEMENT, RIGHT-OF-WAY
and
SURFACE USE AGREEMENT

This Easement, Right-of-Way and Surface Use Agreement ("Agreement") is entered into this 1st day of March, 2008 by and between Brad Lee Nelson and Joann H. Nelson, Co-Trustees of the Brad and Joann Nelson Family Trust, dated February 28, 1991, whose address is P.O. Box 638, Roosevelt, Utah 84066, ("Surface Owner," whether one or more) and Newfield Production Company, a Texas corporation ("NEWFIELD"), with offices at 1401 17th Street, Suite #1000, Denver, Colorado 80202, covering certain lands, (the "Lands") situated in Duchesne and Uintah Counties, Utah described as follows:

Township 8 South, Range 17 West
Section 22: NE, E/2NW, N/2SW, SESW, S/2SE
Section 23: SWSW
Duchesne County, Utah

Township 8 South, Range 17 West
Section 23: SESW
Uintah County, Utah

being 520 acres more or less,

For and in consideration of the sum of ten dollars (\$10.00), and other valuable consideration, the receipt and sufficiency of which are hereby acknowledged, the undersigned hereby agree to the terms and provisions set forth as follows:

1. Compensation for Well; Release of All Claims

NEWFIELD shall pay to Surface Owner the sum as set forth in and according to the terms of that certain Letter Agreement for Easement, Right-of Way and Surface Use by and between Surface Owner and NEWFIELD, dated March 1, 2008, as full payment and satisfaction for any and all detriment, depreciation, injury or damage of any nature to the Lands or growing crops thereon that may occur as a result of NEWFIELD's drilling or completion operations or its continuing activities for the production or transportation of oil, gas, or other hydrocarbons or products associated with the foregoing including, but not limited to, surface use, access, pipelines, gathering lines, pipeline interconnections, and any and all other reasonable or customary uses of land related to said operations or activities.

2. Grant of Right of Way and Easement

Surface Owner hereby grants, bargains, leases, assigns, and conveys to NEWFIELD an easement and right-of-way for the purpose of construction, using and maintaining access roads, locations for surface equipment and subsurface gathering lines for each well drilled upon the Lands, pipelines, and pipeline interconnections for two years from date of this agreement and so long thereafter as NEWFIELD's oil and gas leases remain in effect.

This Agreement shall be binding upon the respective heirs, executors, administrators, successors, and assigns of the undersigned.

These Parties hereto have executed this document effective as of the day first above written.

SURFACE OWNER:
BRAD AND JOANN NELSON FAMILY TRUST
DATED FEBRUARY 28, 1991

NEWFIELD PRODUCTION COMPANY

By: Brad Lee Nelson
Brad Lee Nelson, Co-Trustee

By: _____
Gary D. Packer, President

By: Joann H. Nelson
Joann H. Nelson, Co-Trustee


STATE OF UTAH)
)ss
COUNTY OF Duchesne)

This instrument was acknowledged before me this 4 day of March, 2008 by

Witness my hand and official seal.

My commission expires July 5, 2011

David Allred
Notary Public



STATE OF COLORADO)
)ss
COUNTY OF Denver)

This instrument was acknowledged before me this _____, 2008 by
Gary D. Packer, as President of Newfield Production Company, a Texas corporation, on behalf of the
corporation.

Witness my hand and official seal.

Notary Public

My commission expires _____

**NEWFIELD PRODUCTION COMPANY
GREATER MONUMENT BUTTE L-22-8-17
AT SURFACE: SW/NE SECTION 22, T8S, R17E
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site Greater Monument Butte L-22-8-17 located in the SW 1/4 NE 1/4 Section 22, T8S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly – 6.8 miles \pm to it's junction with an existing road to the east; proceed in a easterly direction – 3.7 miles \pm to it's junction with the access road to the existing 32-22-8-17 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionally off of the existing 32-22-8-17 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 41-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Brad Nelson.

See attached Memorandum of Surface Use Agreement and Easement ROW..

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey will be the forthcoming. The Paleontological Resource Survey for this area is attached. Survey prepared by, Wade E. Miller, 10/22/10. See attached report cover page, Exhibit "D".

Surface Flow Line

Newfield requests 1,060' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. For all new wells, Newfield. **Refer to Topographic Map "D"** for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures:

Clearing and Grading: No clearing or grading of the ROW will be required. The centerline of the proposed route will be staked prior to installation. Flow lines shall be placed as close to existing roads as possible without interfering with normal road travel or road maintenance activities. Due to the proximity of existing facilities, no temporary use or construction/storage areas are anticipated. If necessary, temporary use or construction/storage areas will be identified on a topographic map included in the approved permit.

Installation: The proposed flow lines will be installed 4-6" above the ground. For portions along existing two-track and primary access roads, lengths of pipe will be strung out in the borrow ditch, welded together, and rolled or dragged into place with heavy equipment. For pipelines that are installed cross-country (not along existing or proposed roads), travel along the lines will be infrequent and for maintenance needs only. No installation activities will be performed during periods when the soil is too wet to adequately support installation equipment. If such equipment creates ruts in excess of three (3) inches deep, the soil will be deemed too wet to adequately support the equipment.

Termination and Final Reclamation: After abandonment of the associated production facilities, the flow lines will be cut and removed, and any incidental surface disturbance reclaimed. Reclamation procedures will follow those outlined in the Ute Tribe Green River Development Program Standard Operating Practices (SOP).

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the Greater Monument Butte L-22-8-17, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the Greater Monument Butte L-22-8-17, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Tim Eaton
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that Newfield Production Company is considered to be the operator of well #L-22-8-17, SW/NE Section 22, T8S, R17E, Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

11/2/10
Date


Mandie Crozier
Regulatory Specialist
Newfield Production Company

2-M SYSTEM

Blowout Prevention Equipment Systems






EXHIBIT C

API Number: 4301350464
Well Name: Greater Monument Butte L-22-8-17
Township 08.0 S Range 17.0 E Section 22
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
Map Produced by Diana Mason



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

November 5, 2010

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2010 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2010 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-50458	GMBU R-19-8-17 Sec 19 T08S R17E 1950 FSL 1985 FEL	BHL Sec 19 T08S R17E 1265 FSL 2585 FEL
43-013-50459	GMBU Q-19-8-17 Sec 19 T08S R17E 0646 FSL 1963 FWL	BHL Sec 19 T08S R17E 1320 FSL 1385 FWL
43-013-50460	GMBU D-30-8-17 Sec 19 T08S R17E 0629 FSL 1950 FWL	BHL Sec 30 T08S R17E 0011 FNL 1299 FWL
43-013-50461	GMBU H-30-8-17 Sec 30 T08S R17E 0634 FNL 1793 FWL	BHL Sec 30 T08S R17E 1668 FNL 2398 FEL
43-013-50462	GMBU H-22-8-17 Sec 22 T08S R17E 1026 FNL 2058 FWL	BHL Sec 22 T08S R17E 1788 FNL 2553 FEL
43-013-50463	GMBU I-22-8-17 Sec 22 T08S R17E 1989 FNL 1989 FEL	BHL Sec 22 T08S R17E 1230 FNL 1203 FEL
43-013-50464	GMBU L-22-8-17 Sec 22 T08S R17E 2007 FNL 2000 FEL	BHL Sec 22 T08S R17E 2547 FNL 1004 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2010.11.05 08:03:08 -06'00'

'APIWellNo:43013504640000'

bcc: File - Greater Monument Butte Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:11-5-10



November 4, 2010

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
Greater Monument Butte L-22-8-17
Greater Monument Butte (Green River) Unit

Surface Hole: T8S-R17E Section 22: SWNE (UTU-77233)
2007' FNL 2000' FEL

Bottom Hole: T8S-R17E Section 22: SENE (UTU-77233)
2547' FNL 1004' FEL

Duchesne County, Utah

Dear Ms. Mason;

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 11/2/10, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield Certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

Should you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink, appearing to read "Shane Gillespie".

Shane Gillespie
Land Associate

Form 3160-3
(August 2007)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER


FORM APPROVED
OMB No. 1004-0137
Expires July 31, 2010

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-77233
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name NA
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. Greater Monument Butte
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Greater Monument Butte L-22-8-17
3b. Phone No. (include area code) (435) 646-3721		9. API Well No.
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SW/NE 2007' FNL 2000' FEL Sec. 22, T8S R17E (UTU-77233) At proposed prod. zone SE/NE 2547' FNL 1004' FEL Sec. 22, T8S R17E (UTU-77233)		10. Field and Pool, or Exploratory Monument Butte
11. Sec., T. R. M. or Blk. and Survey or Area Sec. 22, T8S R17E		12. County or Parish Duchesne
13. State UT		
14. Distance in miles and direction from nearest town or post office* Approximately 11.9 miles southeast of Myton, UT	15. Distance from proposed* location to nearest property or lease line, ft. Approx. 1004' f/lse, 2547' f/unit (Also to nearest drig. unit line, if any)	16. No. of acres in lease 560.00
17. Spacing Unit dedicated to this well 20 Acres	18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 933'	19. Proposed Depth 6,735'
20. BLM/BIA Bond No. on file WYB000493	21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5124' GL	22. Approximate date work will start* 1st Qtr. 2011
23. Estimated duration (7) days from SPUD to rig release		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 11/2/10
Title Regulatory Specialist		
Approved by (Signature)	Name (Printed/Typed)	Date
Title Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.


(Continued on page 2)

*(Instructions on page 2)

T8S, R17E, S.L.B.&M.

N89°31'W - 79.96 (G.L.O.)

S89°21'03"W - 5288.46' (Meas.)



◆ = SECTION CORNERS LOCATED


BASIS OF ELEV; Elevations are base on
LOCATION: an N.G.S. OPUS Correction.
LAT. 40°04'09.56" LONG. 110°00'43.28"
(Tristate Aluminum Cap) Elev. 5281.57'

L-22-8-17
(Surface Location) NAD 83
LATITUDE = 40° 06' 18.71"
LONGITUDE = 109° 59' 24.97"

NEWFIELD EXPLORATION COMPANY

WELL LOCATION, L-22-8-17, LOCATED AS SHOWN IN THE SW 1/4 NE 1/4 OF SECTION 22, T8S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, L-22-8-17, LOCATED AS SHOWN IN THE SE 1/4 NE 1/4 OF SECTION 22, T8S, R17E, S.L.B.&M. DUCHESNE COUNTY, UTAH.



NOTES:

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.


THIS IS TO CERTIFY THAT THE ABOVE PLOT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STACY W.
REGISTERED LAND SURVEYOR
REGISTRATION NO. 10000
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 08-13-10	SURVEYED BY: D.G.
DATE DRAWN: 09-30-10	DRAWN BY: M.W.
REVISED:	SCALE: 1" = 1000'



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

I-22-8-17 (Proposed Well)
L-22-8-17 (Proposed Well)
32-22-8-17 (Existing Well)
SEC. 22, T8S, R17E, S.L.B.&M. Duchsene County, UT.

TOPOGRAPHIC MAP

SHEET

B

DRAWN BY: C.H.M.

DATE: 09-21-2010

SCALE: 1" = 2,000'

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator	NEWFIELD PRODUCTION COMPANY				
Well Name	Greater Monument Butte L-22-8-17				
API Number	43013504640000	APD No	3119	Field/Unit	MONUMENT BUTTE
Location: 1/4,1/4	SWNE	Sec	22	Tw	8.0S Rng 17.0E 2007 FNL 2000 FEL
GPS Coord (UTM)	Surface Owner Brad and Joann Nelson				

Participants

Floyd Bartlett (DOGM), Tim Eaton (Newfield) and Kent Nelson (Representing Surface Owner)

Regional/Local Setting & Topography

The proposed Greater Monument Butte I-22-8-17 and Greater Monument Butte L-22-8-17 oil wells are directional wells to be drilled from the existing pad of the Monument Federal 32-22Y-8-17 water injection well. The pad is planned to be extended about 31 feet to the east. No significant impacts should occur with this expansion, however on-site borrow is not available for the fill for this expansion. If the expansion occurs fill would have to be obtained from the near-by area with consent on the land owner of hauled to the area. An alternative to extending the pad is to drill the wells with Newfield's small rig. Either option appears to be ok. The reserve pit will be re-dug in approximately the original location. The wells are on 20-acre spacing.

The site should be a suitable for drilling and operating the proposed additional wells.

Brad and Joann Nelson own the surface.

Surface Use Plan

Current Surface Use

Grazing
Existing Well Pad

New Road Miles	Well Pad	Src Const Material	Surface Formation
	Width Length		

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

Soil Type and Characteristics

Erosion Issues N

Sedimentation Issues N

Site Stability Issues N

Drainage Diversion Required? N

Berm Required? Y

Erosion Sedimentation Control Required? N

Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N

Reserve Pit

Site-Specific Factors

Site Ranking

Distance to Groundwater (feet)	25 to 75	15
Distance to Surface Water (feet)	300 to 1000	2
Dist. Nearest Municipal Well (ft)	>5280	0
Distance to Other Wells (feet)		20
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)		0
Affected Populations		
Presence Nearby Utility Conduits	Not Present	0
Final Score		52

1 Sensitivity Level

Characteristics / Requirements

A reserve pit will be re-dug in approximately the original location. Its dimensions are 80' x 40' x 8' deep. A 16 mil liner with an appropriate sub-liner is required.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y

Other Observations / Comments

Floyd Bartlett
Evaluator

11/23/2010
Date / Time

Application for Permit to Drill

Statement of Basis

11/29/2010

Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
3119	43013504640000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Brad and Joann Nelson	
Well Name	Greater Monument Butte L-22-8-17		Unit	GMBU (GRRV)	
Field	MONUMENT BUTTE		Type of Work	DRILL	
Location	SWNE 22 8S 17E S 2007 FNL 2000 FEL GPS Coord (UTM)		586122E	4439713N	

Geologic Statement of Basis

The mineral rights for the proposed well are owned by the Federal Government. The BLM will be the agency responsible for evaluating and approving the proposed drilling, casing and cement programs.

Brad Hill
APD Evaluator

11/29/2010
Date / Time

Surface Statement of Basis

The proposed Greater Monument Butte I-22-8-17 and Greater Monument Butte L-22-8-17 oil wells are directional wells to be drilled from the existing pad of the Monument Federal 32-22Y-8-17 water injection well. The pad is planned to be extended about 31 feet to the east. No significant impacts should occur with this expansion, however on-site borrow is not available for the fill for this expansion. If the expansion occurs fill would have to be obtained from the near-by area with consent on the land owner of hauled to the area. An alternative to extending the pad is to drill the wells with Newfield's small rig. Either option appears to be ok. The reserve pit will be re-dug in approximately the original location. The wells are on 20-acre spacing.

The site should be a suitable for drilling and operating the proposed additional wells.

Brad and Joann Nelson own the surface. Kent Nelson, a son, attended the pre-site visit. Mr. Nelson had no concerns regarding the proposal.

The minerals are owned by the United States Government and administered by the Bureau of Land Management. Ms. Christina Cimiluca and Ms. Janna Simonsen previously visited the site with Mr. Tim Eaton of Newfield. They had no concerns or recommendations.

Floyd Bartlett
Onsite Evaluator

11/23/2010
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/3/2010

API NO. ASSIGNED: 43013504640000

WELL NAME: Greater Monument Bute L-22-8-17

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: SWNE 22 080S 170E

Permit Tech Review: ☒

SURFACE: 2007 FNL 2000 FEL

Engineering Review: ☐

BOTTOM: 2547 FNL 1004 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.10521

LONGITUDE: -109.98955

UTM SURF EASTINGS: 586122.00

NORTHINGS: 4439713.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-77233

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ **PLAT**

☒ **Bond:** FEDERAL - WYB000493

☐ **Potash**

☐ **Oil Shale 190-5**

☐ **Oil Shale 190-3**

☐ **Oil Shale 190-13**

☒ **Water Permit:** 437478

☐ **RDCC Review:**

☒ **Fee Surface Agreement**

☐ **Intent to Commingle**

Commingle Approved

LOCATION AND SITING:

☐ **R649-2-3.**

Unit: GMBU (GRRV)

☐ **R649-3-2. General**

☐ **R649-3-3. Exception**

☒ **Drilling Unit**

Board Cause No: R649-3-11


Effective Date:

Siting:

☒ **R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations:
4 - Federal Approval - dmason
5 - Statement of Basis - bhill
15 - Directional - dmason
27 - Other - bhill



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Greater Monument Bute L-22-8-17
API Well Number: 43013504640000
Lease Number: UTU-77233
Surface Owner: FEE (PRIVATE)
Approval Date: 11/29/2010

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <https://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER


FORM APPROVED
OMB No. 1004-0137
Expires July 31, 2010


1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-77233
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name NA
2. Name of Operator Newfield Production Company		7. If Unit or CA Agreement, Name and No. Greater Monument Butte
3a. Address Route #3 Box 3630, Myton UT 84052		8. Lease Name and Well No. Greater Monument Butte L-22-8-17
3b. Phone No. (include area code) (435) 646-3721		9. API Well No. 43 013 X50464
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SW/NE 2007' FNL 2000' FEL Sec. 22, T8S R17E (UTU-77233) At proposed prod. zone SE/NE 2547' FNL 1004' FEL Sec. 22, T8S R17E (UTU-77233)		10. Field and Pool, or Exploratory Monument Butte
14. Distance in miles and direction from nearest town or post office* Approximately 11.9 miles southeast of Myton, UT		11. Sec., T. R. M. or Blk. and Survey or Area Sec. 22, T8S R17E
15. Distance from proposed* location to nearest property or lease line, ft. Approx. 1004' f/lse, 2547' f/unit (Also to nearest drig. unit line, if any)	16. No. of acres in lease 560.00	17. Spacing Unit dedicated to this well 20 Acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 933'	19. Proposed Depth 6,735'	20. BLM/BIA Bond No. on file WYB000493
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5124' GL	22. Approximate date work will start* 1st Qtr. 2011	23. Estimated duration (7) days from SPUD to rig release

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed/Typed) Mandie Crozier	Date 11/2/10
Title Regulatory Specialist		

Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date MAR 25 2011
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

NOTICE OF APPROVAL

RECEIVED

RECEIVED

NOV 05 2010

MAR 29 2011

BLM VERNAL, UTAH

DIV. OF OIL, GAS & MIN.

UDOGM



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4401



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Newfield Production Company	Location:	SWNE, Sec. 22, T8S, R17E (S) SENE, Sec. 22, T8S, R17E (B)
Well No:	Greater Monument Butte L-22-8-17	Lease No:	UTU-77233
API No:	43-013-50464	Agreement:	Greater Monument Butte Unit

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

CONDITIONS OF APPROVAL:

<i>Company/Operator:</i>	Newfield Production Company
<i>Well Name & Number:</i>	Federal L-22-8-17
<i>Surface Ownership:</i>	Brad Lee and Joann Nelson
<i>Lease Number:</i>	UTU-77233
<i>Location:</i>	SWNE Section 22, T8S R17E

- A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be installed and maintained in the reserve pit.
- Any deviation from submitted APD's and ROW applications the operator will notify the BLM in writing and will receive written authorization of any such change with appropriate authorization.
- All operator employees and/or authorized personnel (sub-contractors) in the field will have approved applicable APD's and ROW permits/authorizations on their person(s) during all phases of construction.
- All vehicular traffic, personnel movement, construction/restoration operations shall be confined to the area examined and approved, and to the existing roadways and/or evaluated access routes.
- All permanent surface equipment (meaning on site for six months or longer) will be painted Covert Green to match the surrounding landscape color unless otherwise authorized. This will include all facilities except those required to comply with Occupational Safety and Health Act (OSHA) regulations.

- Reclamation will be completed in accordance with the re-contouring and reseeding procedures outlined in the Newfield Exploration Company Castle Peak and Eight Mile Flat Reclamation Plan on file with the Vernal Field Office of the BLM, unless otherwise specified by the private surface owner.
- Invasive plant species shall be control.

***DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

SITE SPECIFIC DOWNHOLE COAs:

The operator shall comply with all applicable requirements in the SOP (version: "Greater Monument Butte Green River Development Program", June 24, 2008). The operator shall also comply with applicable laws and regulations; with the lease terms, Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the authorized officer.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

Spud
BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 29 Submitted By
Branden Arnold Phone Number 435-401-0223
Well Name/Number GMB L-22-8-17
Qtr/Qtr SW/NE Section 22 Township 8S Range 17E
Lease Serial Number UTU-77233
API Number 43-013-50464

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 4/15/11 9:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 4/18/11 3:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM -FORM 6

OPERATOR: **NEWFIELD PRODUCTION COMPANY**
ADDRESS: **RT. 3 BOX 3630**
MYTON, UT 84052

OPERATOR ACCT. NO. **N2695**

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	17400 ✓	4301350464	GREATER MON BUTTE L-22-8-17	SWNE	22	8S	17E	DUCHESNE	4/15/2011	4/25/11
WELL 1 COMMENTS: GRRV BHL = SENE											
B	99999	17400 ✓	4301350463	GREATER MON BUTTE I-22-8-17	SWNE	22	8S	17E	DUCHESNE	4/14/2011	4/25/11
GRRV BHL = NENE											
B	99999	17400 ✓	4301350462	GREATER MON BUTTE H-22-8-17	NENW	22	8S	17E	DUCHESNE	4/19/2011	4/25/11
GRRV BHL = SWNE											


ACTION CODES (See instructions on back of form)
A - 1 new entity for new well (single well only)
B - well to existing entity (group or unit well)
C - from one existing entity to another existing entity
D - well from one existing entity to a new entity
E - other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

RECEIVED

APR 25 2011

DIV. OF OIL, GAS & MINING

Signature 
Production Clerk **Jentri Park**
04/25/11

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

SUBMIT IN TRIPLICATE - Other Instructions on page 2

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

NEWFIELD PRODUCTION COMPANY

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Section 22 T8S R17E

5. Lease Serial No.

USA UTU-77233

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or

GMBU

8. Well Name and No.

GMBU L-22-8-17

9. API Well No.

4301350464

10. Field and Pool, or Exploratory Area

GREATER MB UNIT

11. County or Parish, State

DUCHESNE, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice _____
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation: (Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 4/15/11 MIRU Ross #29. Spud well @9:00 AM. Drill 360' of 12 1/4" hole with air mist. TIH W/ 8 Jt's 8 5/8" J-55 24# csgr. Set @ 357.62. On 4/18/11 cement with 180 sks of class "G" w/ 2% CaCL2 + 0.25#/sk Cello- Flake Mixed @ 15.8ppg w/ 1.17ft3/sk yield. Returned 6 barrels cement to pit. WOC.

RECEIVED
MAY 10 2011
DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct (Printed/ Typed)

Branden Arnold

Title

Signature

Date

04/18/2011

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on page 2)

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8" CASING SET AT 357.62

LAST CASING 14 SET AT 11
 DATUM 10
 DATUM TO CUT OFF CASING 10
 DATUM TO BRADENHEAD FLANGE 10
 TD DRILLER 360 LOGGER _____
 HOLE SIZE 12 1/4"

OPERATOR Newfield Exploration Company
 WELL GMBU L-22-8-17
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Ross # 29

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION		WT / FT	GRD	THREAD	CONDT	LENGTH
1		wellhead					A	1.42
8	8 5/8"	casing (shoe jt 43.55)		24	J-55	STC	A	347.3
1	8 5/8"	guide shoe					A	0.9
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING				349.62
TOTAL LENGTH OF STRING		349.62	8	LESS CUT OFF PIECE				2
LESS NON CSG. ITEMS		2.32		PLUS DATUM TO T/CUT OFF CSG				10
PLUS FULL JTS. LEFT OUT		0		CASING SET DEPTH				357.62
TOTAL		347.3	8	} COMPARE				
TOTAL CSG. DEL. (W/O THRDS)								
TIMING								
BEGIN RUN CSG.	Spud	9:00 AM	4/15/2011	GOOD CIRC THRU JOB				Yes
CSG. IN HOLE		2:00 AM	4/15/2011	Bbls CMT CIRC TO SURFACE				
BEGIN CIRC		8:17 AM	4/18/2011	RECIPROCATED PIP				No
BEGIN PUMP CMT		8:25 AM	4/18/2011	BUMPED PLUG TO				
BEGIN DSPL. CMT		8:39 AM	4/18/2011					475
PLUG DOWN		8:48 AM	4/18/2011					

[illegible]

COMPANY REPRESENTATIVE

Branden Arnold

DATE **4/18/2011**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-77233
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GMBU
PHONE NUMBER 435.646.3721		8. WELL NAME and NUMBER: GMBU L-22-8-17
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2007 FNL 2000 FEL		9. API NUMBER: 4301350464
OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: , 22, T8S, R17E		10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will 	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 05/23/2011	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above subject well was completed on 5/23/2011, attached is a daily completion status report.

RECEIVED

JUN 02 2011

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Jennifer Peatross TITLE Production Technician
SIGNATURE  DATE 05/25/2011

(This space for State use only)

Daily Activity Report

Format For Sundry

GMBU L-22-8-17**3/1/2011 To 7/30/2011****5/9/2011 Day: 1****Completion**

Rigless on 5/9/2011 - Rigged up Perforators WLT with lubricator. Ran CBL under pressure. WLTD was 6615' with TOC at 49'. Ran in hole with 3-1/8" ported gun and perforated CP5 sands as shown in perforation report. SWIFN. - Nipple up frac head and Weatherford BOPs. Rig up Preferred Hot Oiler and test casing, frac head, frac valves and BOP to 4500 psi. Rig up Perforators WLT with lubricator. Run CBL under pressure. WLTD was 6615' with TOC at 49'. Run in hole with 3-1/8" ported guns and perforate CP5 sands as shown in perforation report. Rig down WLT and hot oiler. SIWFN w/ 157 BWTR.

Daily Cost: \$0**Cumulative Cost:** \$9,753

5/12/2011 Day: 2**Completion**

Rigless on 5/12/2011 - Frac Stgs 1-5. Flowback to pit. - RU Extreme wireline. Set CFTP @ 6360' & perf stg 2- CP2/CP1/CP.5 sds as shown in perforation report. RU BJ Services. Frac stg 2- CP2/CP1/CP.5 sds as shown in stimulation report. 1179.2 BWTR. - RU Extreme wireline. Set CFTP @ 5340' & perf stg 3- DS3 sds as shown in perforation report. RU BJ Services. Frac stg 3- DS3 sands as shown in stimulation report. 1491.3 BWTR. - RU The Perforators wireline. Set CFTP @ 4950' & perf stg 4- GB6/GB2 sds as shown in perforation report. RU BJ Services. Frac stg 4- GB6/GB2 sds as shown in stimulation report. 1848.9 BWTR. - Crew travel and safety meeting. RU BJ Services. Frac stg 1- CP5 sds as shown in stimulation report. 550.4 BWTR. - RU Extreme wireline. Set CFTP @ 4645' & perf stg 5- GG1 sds as shown in perforation report. RU BJ Services. Frac stg 5- GG1 sds as shown in stimulation report. 2294.3 BWTR - RD BJ Services & Extreme wireline. Open well to pit for immediate flowback @ approx. 3 bpm. Well flowed for 6 hrs & died. Recovered 1080 bbls. SWIFN. 1214.3 BWTR.

Daily Cost: \$0**Cumulative Cost:** \$127,509

5/18/2011 Day: 3**Completion**

WWS #3 on 5/18/2011 - MIRUWOR. Change out Frac BOPS and NU Shaffer BOPS. RU Floor and tbq Equipment. SWIFN. - Safety Meeting, discussed location hazards, recent NFX incidents, job procedure, emergency plans, meeting point. MIROWOR. SICP @ 90 PSI. BO well and ND Frac BOPS. RU Shaffer BOPS, floor, and tbq equipment. SWIFN @ 16:00.

Daily Cost: \$0**Cumulative Cost:** \$129,999

5/19/2011 Day: 4**Completion**

WWS #3 on 5/19/2011 - DO/CO to PBTD. - Crew travel and safety meeting. Wait on tbq to unload w/ well dead. PU and tallied new 4-3/4" chomp bit and 2-7/8" tbq to tag plg @ 4645'. RU nabors swivel and and DO plg in 18 min. Cont to PU and RIH to tag plg @ 4950'. DO plg in 20 min. Cont to PU and RIH to tag plg @ 5340'. DO plg in 18 min. Circ well clean. CWI @ 15:30. EOT @ 5368'.

Daily Cost: \$0**Cumulative Cost:** \$136,474

5/20/2011 Day: 5**Completion**

WWS #3 on 5/20/2011 - Cont. DO/CO to PBTD. Swab back fld and POOH. RBIH w/Production string. - Crew travel and safety meeting. W/well dead, Cont Pu and RIH to tag fill @ 6272'. CO to plg @ 6360'. DO in 16 min. Circ well until clean. PU and RIH to tag fill @ 6516'. CO to PBTD @ 6662'. Circ well clean and rack out drill equipment. LD 2 jts - EOT @ 6601'. RU to swab. Make 14 runs to swab back 155 BW w/ no sand and trace oil. FFL @ 1200'. RD swab equip. PU and RIH to tag PBTD with no new fill. Circ well clean and LD extra tbg. POOH w/tbg and LD chomp bit and bit sub. RBIH w/ 2-7/8" BP, collar, 3 jts, 2-7/8" nipple, PBGA, 1 jt, PSN, 1 jt, TAC, and 116 jts 2-7/8" tbg. EOT @ 3630'. CWIFN @ 18:30.

Daily Cost: \$0**Cumulative Cost:** \$142,898

5/23/2011 Day: 6**Completion**

WWS #3 on 5/23/2011 - Cont running Production string and Pump/Rods. Seat pump and test. RDMOWOR, PWOP @ 16:00. - Crew travel and safety meeting. W/ well dead, cont TIH w/ tbg as follows: BP, collar, 3 jts, 2-7/8" nipple, PBGA, 1 jt, PSN, 1 jt, TAC, and 201 jts. ND BOPS, and set TAC w/18000# tension. Land tbg w/ tbg hanger. TAC @ 6269.24'. PSN @ 6302.26'. EOT @ 6435.89'. NU B-1 adapter flange. Change over to run rods, Flush tbg w/ 60 BW. Prep rods and PU and prime Cent Hyd 25-175-RHAC-20-4-21-24 pump w/ 225 max stk. PU and TIH w/ rods as follows: Pump, 1"X4' Stabilizer, 4-1.5" wt bars, 61- 3/4" 8 per guided rods (MMS), 33-3/4" 8 per guided rods, 152- 7/8" 8 per guided rods, 1-4', 6', and 8'- 7/8" pony rod, 1- 1.5"X30' Polish rod. Seat pump, RU pumping unit, fill tbg w/3 BW. Stroke pump w/unit to 800 psi with good pumping action. RDMOWOR. PWOP @ 16:00 w/ 144" stroke length and 5 SPM. - **Finalized**

Daily Cost: \$0**Cumulative Cost:** \$225,438

Pertinent Files: Go to File List

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

Amended

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

5. Lease Serial No.
UTU-77233

a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
Other: _____

2. Name of Operator
NEWFIELD EXPLORATION COMPANY

3. Address
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)
(435) 646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 2007' FNL & 2000' FEL (SW/NE) SEC. 22, T8S, R17E (UTU-77233)

At top prod. interval reported below 2363' FNL & 1333' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233)

At total depth 2536' FNL & 985' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233)

14. Date Spudded
04/15/2011

15. Date T.D. Reached
04/30/2011

16. Date Completed 05/20/2011
☐ D & A ☒ Ready to Prod.

17. Elevations (DF, RKB, RT, GL)*
5124' GL 5136' KB

18. Total Depth: MD 6683'
TVD 6570'

19. Plug Back T.D.: MD 6645'
TVD

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	360'		180 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6669'		300 PRIMLITE		49'	
						416 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@ 6436'	TA @ 6269'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River	4532'	6517'	6511-6517'	.36"	18	
B)			4532-6290'	.34"	111	
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
4532-6517'	Frac w/ 192211#s 20/40 sand in 1377 bbls of Lightning 17 fluid in 5 stages

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
5/27/11	6/6/11	24	→	66	45	25			2-1/2" x 1-3/4" x 20' x 21' x 24' RHAC Pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

RECEIVED

JUL 07 2011

DIV. OF OIL, GAS & MINING

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

SOLD AND USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH GREEN RIVER	7267' 5412'	7338' 7030'		GARDEN GULCH MRK GARDEN GULCH 1	4971' 5163'
				GARDEN GULCH 2 POINT 3	5290' 5619'
				X MRKR Y MRKR	5793' 5834'
				DOUGALS CREEK MRK BI-CARB	5996' 6282'
				B LIMESTONE MARK CASTLE PEAK	6453' 6721'
				BASAL CARBONATE WASATCH	7067' 7175'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: **Drilling Daily Activity**

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Jennifer PeatrossTitle Production TechnicianSignature J PeatrossDate 07/05/2011

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD



NEWFIELD EXPLORATION

USGS Myton SW (UT)

SECTION 22 T8S, R17E


L-22-8-17

Wellbore #1

Design: Actual

Standard Survey Report

09 May, 2011





PayZone Directional Services, LLC.

Survey Report



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 22 T8S, R17E
Well: L-22-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 22 T8S, R17E, SEC 22 T8S, R17E				
Site Position:		Northing:	7,208,900.00 ft	Latitude:	40° 6' 1.964 N
From:	Lat/Long	Easting:	2,062,000.00 ft	Longitude:	109° 59' 34.084 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence:	0.97 °

Well	L-22-8-17, SHL LAT: 40° 06' 18.71, LONG: -109° 59' 24.97					
Well Position	+N/-S	0.0 ft	Northing:	7,210,606.09 ft	Latitude:	40° 6' 18.710 N
	+E/-W	0.0 ft	Easting:	2,062,679.44 ft	Longitude:	109° 59' 24.970 W
Position Uncertainty		0.0 ft	Wellhead Elevation:	5,136.0 ft	Ground Level:	5,124.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/09/27	11.38	65.88	52,387

Design	Actual				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.0	0.0	0.0	117.76	

Survey Program	Date	2011/05/09			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
383.0	6,683.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Survey	Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
	0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
	383.0	0.70	177.30	383.0	-2.3	0.1	1.2	0.18	0.18	0.00
	414.0	0.80	156.20	414.0	-2.7	0.2	1.5	0.94	0.32	-68.06
	445.0	1.10	150.10	445.0	-3.2	0.4	1.9	1.02	0.97	-19.68
	475.0	1.50	156.60	475.0	-3.8	0.7	2.4	1.42	1.33	21.67
	506.0	1.80	147.00	506.0	-4.6	1.2	3.2	1.31	0.97	-30.97
	536.0	1.90	144.90	535.9	-5.4	1.7	4.0	0.40	0.33	-7.00
	567.0	2.20	150.10	566.9	-6.3	2.3	5.0	1.14	0.97	16.77
	597.0	2.80	150.70	596.9	-7.4	2.9	6.1	2.00	2.00	2.00
	628.0	2.90	151.20	627.9	-8.8	3.7	7.4	0.33	0.32	1.61
	659.0	2.80	149.40	658.8	-10.1	4.5	8.7	0.43	-0.32	-5.81
	689.0	3.30	144.80	688.8	-11.5	5.3	10.1	1.85	1.67	-15.33
	719.0	3.60	143.90	718.7	-12.9	6.4	11.7	1.02	1.00	-3.00



Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
750.0	4.10	143.30	749.7	-14.6	7.6	13.5	1.62	1.61	-1.94
781.0	4.40	145.20	780.6	-16.5	9.0	15.6	1.07	0.97	6.13
812.0	4.70	145.20	811.5	-18.5	10.4	17.8	0.97	0.97	0.00
855.0	5.90	140.50	854.3	-21.6	12.8	21.4	2.97	2.79	-10.93
900.0	6.90	138.00	899.0	-25.4	16.1	26.1	2.31	2.22	-5.56
944.0	7.40	137.50	942.7	-29.5	19.7	31.2	1.15	1.14	-1.14
988.0	7.80	137.30	986.3	-33.8	23.7	36.7	0.91	0.91	-0.45
1,032.0	8.30	137.70	1,029.8	-38.3	27.8	42.5	1.14	1.14	0.91
1,076.0	8.80	135.50	1,073.4	-43.1	32.3	48.7	1.36	1.14	-5.00
1,120.0	9.20	134.80	1,116.8	-47.9	37.2	55.2	0.94	0.91	-1.59
1,164.0	9.40	131.10	1,160.2	-52.8	42.4	62.1	1.43	0.45	-8.41
1,208.0	10.20	129.80	1,203.6	-57.6	48.1	69.4	1.89	1.82	-2.95
1,252.0	10.80	128.80	1,246.9	-62.7	54.3	77.3	1.43	1.36	-2.27
1,296.0	11.40	126.90	1,290.0	-67.9	61.0	85.6	1.60	1.36	-4.32
1,340.0	11.30	123.50	1,333.2	-72.9	68.1	94.2	1.54	-0.23	-7.73
1,384.0	11.10	121.00	1,376.3	-77.5	75.3	102.7	1.19	-0.45	-5.68
1,428.0	11.20	117.10	1,419.5	-81.6	82.7	111.2	1.73	0.23	-8.86
1,472.0	11.70	116.30	1,462.6	-85.5	90.5	119.9	1.19	1.14	-1.82
1,516.0	11.90	114.50	1,505.7	-89.4	98.7	128.9	0.95	0.45	-4.09
1,560.0	11.90	115.10	1,548.8	-93.2	106.9	138.0	0.28	0.00	1.36
1,604.0	12.10	115.40	1,591.8	-97.1	115.2	147.1	0.48	0.45	0.68
1,648.0	12.20	114.50	1,634.8	-101.0	123.6	156.4	0.49	0.23	-2.05
1,692.0	12.50	114.10	1,677.8	-104.9	132.1	165.8	0.71	0.68	-0.91
1,736.0	12.30	114.80	1,720.8	-108.8	140.7	175.2	0.57	-0.45	1.59
1,780.0	12.60	113.90	1,763.7	-112.7	149.4	184.7	0.81	0.68	-2.05
1,824.0	12.80	113.40	1,806.7	-116.6	158.2	194.3	0.52	0.45	-1.14
1,868.0	12.70	114.10	1,849.6	-120.5	167.1	204.0	0.42	-0.23	1.59
1,912.0	12.80	113.40	1,892.5	-124.4	176.0	213.7	0.42	0.23	-1.59
1,956.0	13.00	111.30	1,935.4	-128.1	185.1	223.5	1.16	0.45	-4.77
2,000.0	12.70	111.60	1,978.3	-131.7	194.2	233.2	0.70	-0.68	0.68
2,044.0	13.00	114.30	2,021.2	-135.5	203.2	242.9	1.53	0.68	6.14
2,088.0	13.20	113.40	2,064.0	-139.5	212.3	252.9	0.65	0.45	-2.05
2,132.0	13.00	114.20	2,106.9	-143.6	221.5	262.8	0.61	-0.45	1.82
2,176.0	12.90	111.90	2,149.8	-147.4	230.5	272.7	1.19	-0.23	-5.23
2,220.0	12.40	112.40	2,192.7	-151.1	239.5	282.3	1.16	-1.14	1.14
2,264.0	12.20	113.40	2,235.7	-154.7	248.1	291.6	0.66	-0.45	2.27
2,308.0	11.90	111.90	2,278.7	-158.2	256.6	300.7	0.99	-0.68	-3.41
2,352.0	11.30	110.40	2,321.8	-161.4	264.8	309.5	1.53	-1.36	-3.41
2,396.0	10.80	110.10	2,365.0	-164.4	272.7	317.9	1.14	-1.14	-0.68
2,440.0	10.50	110.60	2,408.2	-167.2	280.4	326.0	0.71	-0.68	1.14
2,484.0	10.10	110.50	2,451.5	-170.0	287.7	333.8	0.91	-0.91	-0.23
2,528.0	10.30	109.70	2,494.8	-172.6	295.0	341.5	0.56	0.45	-1.82
2,572.0	10.80	109.10	2,538.1	-175.3	302.6	349.5	1.16	1.14	-1.36
2,615.0	11.30	109.70	2,580.3	-178.0	310.4	357.6	1.19	1.16	1.40
2,659.0	11.60	111.90	2,623.4	-181.1	318.6	366.3	1.20	0.68	5.00
2,703.0	11.50	112.30	2,666.5	-184.5	326.7	375.0	0.29	-0.23	0.91
2,747.0	11.30	113.40	2,709.7	-187.8	334.8	383.7	0.67	-0.45	2.50
2,792.0	11.10	115.10	2,753.8	-191.4	342.7	392.4	0.86	-0.44	3.78
2,836.0	11.30	119.30	2,797.0	-195.3	350.3	401.0	1.91	0.45	9.55
2,880.0	12.30	119.90	2,840.0	-199.8	358.1	410.0	2.29	2.27	1.36
2,924.0	12.50	123.00	2,883.0	-204.7	366.2	419.4	1.58	0.45	7.05
2,968.0	12.70	121.30	2,925.9	-209.8	374.3	429.0	0.96	0.45	-3.86
3,012.0	12.80	120.90	2,968.9	-214.8	382.6	438.7	0.30	0.23	-0.91
3,056.0	13.10	116.70	3,011.7	-219.6	391.3	448.5	2.24	0.68	-9.55



PayZone Directional Services, LLC.

Survey Report

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 22 T8S, R17E
Well: L-22-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,100.0	13.80	117.00	3,054.5	-224.2	400.4	458.7	1.60	1.59	0.68
3,144.0	14.00	117.20	3,097.2	-229.0	409.8	469.3	0.47	0.45	0.45
3,188.0	14.20	117.90	3,139.9	-234.0	419.3	480.0	0.60	0.45	1.59
3,231.0	13.70	116.30	3,181.7	-238.7	428.5	490.4	1.47	-1.16	-3.72
3,275.0	12.40	111.70	3,224.5	-242.7	437.6	500.3	3.78	-2.95	-10.45
3,319.0	11.70	110.40	3,267.5	-246.0	446.2	509.4	1.71	-1.59	-2.95
3,363.0	11.70	110.80	3,310.6	-249.2	454.5	518.3	0.18	0.00	0.91
3,407.0	11.70	111.50	3,353.7	-252.4	462.8	527.1	0.32	0.00	1.59
3,451.0	12.10	111.70	3,396.8	-255.7	471.3	536.2	0.91	0.91	0.45
3,495.0	11.90	112.90	3,439.8	-259.2	479.7	545.3	0.73	-0.45	2.73
3,539.0	12.40	113.10	3,482.8	-262.8	488.3	554.5	1.14	1.14	0.45
3,583.0	13.00	112.30	3,525.8	-266.6	497.2	564.1	1.42	1.36	-1.82
3,627.0	13.40	114.50	3,568.6	-270.6	506.4	574.1	1.46	0.91	5.00
3,671.0	12.50	114.80	3,611.5	-274.7	515.4	584.0	2.05	-2.05	0.68
3,715.0	12.10	115.60	3,654.5	-278.7	523.9	593.4	0.99	-0.91	1.82
3,759.0	12.40	117.80	3,697.5	-282.9	532.2	602.7	1.26	0.68	5.00
3,803.0	12.80	117.50	3,740.4	-287.3	540.7	612.3	0.92	0.91	-0.68
3,847.0	12.60	117.60	3,783.3	-291.8	549.3	622.0	0.46	-0.45	0.23
3,891.0	12.00	118.30	3,826.3	-296.2	557.6	631.3	1.41	-1.36	1.59
3,935.0	11.80	117.60	3,869.4	-300.4	565.6	640.4	0.56	-0.45	-1.59
3,979.0	11.60	115.10	3,912.5	-304.4	573.6	649.3	1.24	-0.45	-5.68
4,023.0	11.30	117.30	3,955.6	-308.2	581.4	658.1	1.20	-0.68	5.00
4,067.0	11.30	118.10	3,998.7	-312.3	589.0	666.7	0.36	0.00	1.82
4,112.0	11.60	120.60	4,042.8	-316.6	596.8	675.6	1.29	0.67	5.56
4,156.0	11.30	120.80	4,086.0	-321.1	604.3	684.3	0.69	-0.68	0.45
4,200.0	11.00	118.10	4,129.1	-325.3	611.7	692.8	1.37	-0.68	-6.14
4,244.0	10.40	117.20	4,172.4	-329.1	619.0	701.0	1.42	-1.36	-2.05
4,288.0	10.20	116.80	4,215.6	-332.6	626.0	708.9	0.48	-0.45	-0.91
4,332.0	9.90	119.10	4,259.0	-336.2	632.8	716.5	1.14	-0.68	5.23
4,376.0	10.00	121.00	4,302.3	-340.0	639.3	724.1	0.78	0.23	4.32
4,420.0	10.30	120.30	4,345.6	-344.0	646.0	731.9	0.74	0.68	-1.59
4,464.0	10.40	119.40	4,388.9	-347.9	652.9	739.8	0.43	0.23	-2.05
4,508.0	10.60	117.30	4,432.2	-351.7	659.9	747.8	0.98	0.45	-4.77
4,552.0	10.60	119.50	4,475.4	-355.6	667.0	755.9	0.92	0.00	5.00
4,596.0	10.50	119.50	4,518.7	-359.6	674.1	763.9	0.23	-0.23	0.00
4,640.0	10.80	117.80	4,561.9	-363.5	681.2	772.1	0.99	0.68	-3.86
4,684.0	10.50	116.60	4,605.2	-367.2	688.4	780.2	0.85	-0.68	-2.73
4,728.0	10.50	117.00	4,648.4	-370.8	695.6	788.2	0.17	0.00	0.91
4,772.0	10.30	115.70	4,691.7	-374.3	702.7	796.2	0.70	-0.45	-2.95
4,816.0	10.50	116.40	4,735.0	-377.8	709.8	804.1	0.54	0.45	1.59
4,860.0	10.10	116.70	4,778.3	-381.3	716.9	812.0	0.92	-0.91	0.68
4,904.0	9.60	118.80	4,821.6	-384.8	723.5	819.5	1.40	-1.14	4.77
4,948.0	9.00	123.80	4,865.0	-388.5	729.6	826.6	2.29	-1.36	11.36
4,992.0	9.10	124.20	4,908.5	-392.4	735.3	833.5	0.27	0.23	0.91
5,036.0	9.30	126.80	4,951.9	-396.5	741.1	840.4	1.05	0.45	5.91
5,080.0	9.90	125.80	4,995.3	-400.8	747.0	847.7	1.42	1.36	-2.27
5,124.0	9.70	123.70	5,038.7	-405.1	753.1	855.1	0.93	-0.45	-4.77
5,168.0	9.80	123.30	5,082.0	-409.2	759.3	862.5	0.27	0.23	-0.91
5,212.0	9.70	119.20	5,125.4	-413.0	765.7	870.0	1.59	-0.23	-9.32
5,256.0	9.70	118.20	5,168.8	-416.6	772.2	877.4	0.38	0.00	-2.27
5,300.0	10.20	114.40	5,212.1	-420.0	779.0	885.0	1.88	1.14	-8.64
5,344.0	10.70	110.90	5,255.4	-423.0	786.4	892.9	1.84	1.14	-7.95
5,388.0	10.70	109.40	5,298.6	-425.8	794.1	901.0	0.63	0.00	-3.41
5,432.0	10.80	112.90	5,341.8	-428.8	801.7	909.2	1.50	0.23	7.95



PayZone Directional Services, LLC.

Survey Report

COMPASS

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 22 T8S, R17E
Well: L-22-8-17
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,476.0	10.60	115.20	5,385.1	-432.1	809.2	917.3	1.07	-0.45	5.23
5,485.4	10.58	115.01	5,394.4	-432.9	810.7	919.0	0.44	-0.23	-2.03
L-22-8-17 TGT									
5,520.0	10.50	114.30	5,428.3	-435.5	816.5	925.4	0.44	-0.23	-2.05
5,564.0	10.40	115.50	5,471.6	-438.9	823.7	933.3	0.54	-0.23	2.73
5,608.0	10.30	114.80	5,514.9	-442.2	830.9	941.2	0.37	-0.23	-1.59
5,652.0	10.40	115.00	5,558.2	-445.6	838.1	949.1	0.24	0.23	0.45
5,696.0	10.50	113.60	5,601.4	-448.8	845.3	957.1	0.62	0.23	-3.18
5,740.0	10.70	114.00	5,644.7	-452.1	852.7	965.2	0.48	0.45	0.91
5,784.0	11.00	115.20	5,687.9	-455.6	860.3	973.4	0.85	0.68	2.73
5,828.0	10.80	117.40	5,731.1	-459.2	867.7	981.7	1.05	-0.45	5.00
5,872.0	10.40	115.60	5,774.4	-462.8	875.0	989.8	1.18	-0.91	-4.09
5,916.0	10.60	118.00	5,817.6	-466.5	882.1	997.9	1.09	0.45	5.45
5,960.0	10.70	117.20	5,860.9	-470.2	889.3	1,006.0	0.41	0.23	-1.82
6,004.0	11.40	118.60	5,904.1	-474.2	896.8	1,014.4	1.70	1.59	3.18
6,048.0	12.10	117.30	5,947.1	-478.4	904.7	1,023.4	1.70	1.59	-2.95
6,092.0	12.50	116.20	5,990.1	-482.6	913.1	1,032.7	1.05	0.91	-2.50
6,136.0	12.30	112.80	6,033.1	-486.5	921.7	1,042.2	1.72	-0.45	-7.73
6,180.0	11.20	113.50	6,076.2	-490.0	929.9	1,051.1	2.52	-2.50	1.59
6,224.0	11.30	113.40	6,119.3	-493.4	937.8	1,059.7	0.23	0.23	-0.23
6,268.0	11.40	114.60	6,162.5	-497.0	945.7	1,068.3	0.58	0.23	2.73
6,312.0	11.30	115.60	6,205.6	-500.6	953.5	1,077.0	0.50	-0.23	2.27
6,356.0	11.30	116.50	6,248.8	-504.4	961.3	1,085.6	0.40	0.00	2.05
6,400.0	11.00	115.20	6,291.9	-508.1	968.9	1,094.1	0.89	-0.68	-2.95
6,444.0	10.30	115.30	6,335.2	-511.6	976.3	1,102.2	1.59	-1.59	0.23
6,488.0	10.50	117.10	6,378.4	-515.1	983.4	1,110.1	0.87	0.45	4.09
6,532.0	10.40	115.60	6,421.7	-518.7	990.5	1,118.1	0.66	-0.23	-3.41
6,576.0	10.00	115.70	6,465.0	-522.0	997.6	1,125.9	0.91	-0.91	0.23
6,629.0	10.00	113.20	6,517.2	-525.8	1,005.9	1,135.1	0.82	0.00	-4.72
6,683.0	10.00	113.20	6,570.4	-529.5	1,014.6	1,144.4	0.00	0.00	0.00

Wellbore Targets

Target Name

- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- Shape									
L-22-8-17 TGT	0.00	0.00	5,400.0	-413.8	786.2	7,210,205.60	2,063,472.52	40° 6' 14.620 N	109° 59' 14.851 W
- actual wellpath misses by 31.6ft at 5485.4ft MD (5394.3 TVD, -432.9 N, 810.7 E)									
- Circle (radius 75.0)									

Checked By: _____ Approved By: _____ Date: _____

NEWFIELD





Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 SURVEY: Actual



Azimuths to True North
 Magnetic North: 11.38°

Magnetic Field
 Strength: 52387.2snT
 Dip Angle: 65.88°
 Date: 2010/09/27
 Model: IGRF2010



Design: Actual (L-22-8-17/Wellbore #1)



Created By: Sarah Webb Date: 14:31, May 09 2011
 THIS SURVEY IS CORRECT TO THE BEST OF MY
 KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA.

Daily Activity Report

Format For Sundry

GMBU L-22-8-17**2/1/2011 To 6/30/2011****GMBU L-22-8-17****Waiting on Cement****Date:** 4/18/2011

Ross #29 at 360. Days Since Spud - yield. Returned 6bbls to pit, bump plug to 475psi, BLM and State were notified of spud via email. - On 4/15/11 Ross #29 spud and drilled 360' of 12 1/4" hole, P/U and run 8 jts of 8 5/8" casing set - @ 357.62'KB. On 4/18/11 cement w/BJ w/180 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17

Daily Cost: \$0**Cumulative Cost:** \$58,320

GMBU L-22-8-17**Drill 7 7/8" hole with fresh water****Date:** 4/28/2011

NDSI SS #1 at 2538. 1 Days Since Spud - Pre spud meeting w/ crew and Payzone directional hands - MIRU SET ALL EQUIPMENT W/Liddell trucking - Gain circulation and tag @ 320' - Drill 7 7/8" hole F/320' - 2538', w/ 20 WOB, 160 RPM, 379 GPM, ROP 170 - Surface csg @ 1500 PSI - test good - P/U Security 7 7/8" PDC bit, Payzone directional tools, HWDP - R/U B&C quicktest Test Kelly,safty valve,choke manifold,Pipe and blind rams @ 2000 PSI

Daily Cost: \$0**Cumulative Cost:** \$94,693

GMBU L-22-8-17**Drill 7 7/8" hole with fresh water****Date:** 4/29/2011

NDSI SS #1 at 5838. 2 Days Since Spud - 2gal/min Flow @ 5398' - Drill 7 7/8" hole F/ 2538' to 3945, w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP - Rig Service, Grease Top Drive, Boom and Crown. - Drill 7 7/8" hole F/ 3945 to 5838', w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP

Daily Cost: \$0**Cumulative Cost:** \$121,507

GMBU L-22-8-17**Running casing****Date:** 4/30/2011

NDSI SS #1 at 6683. 3 Days Since Spud - Rig up B&C Quick Tests and Test 5 1/2" Casing Rams to 2,000PSI F/ 10min, tested good - Rig up PSI and run Wireline tools F/ TD to Surface - Laydown Drill Pipe and BHA - Pump 360bbls of Brine - Laydown Drill Pipe to 4,000' - Pump Sweep, Circulate Well F/ Laydown and Logs - Drill 7 7/8" hole F/ 5838' to 6683' TD, w/ 22,000 WOB, 160 RPM, 420 GPM, 130fph ROP - Rig up and Run 159jts J-55 LTC 15.5# 5 1/2" Casing

Daily Cost: \$0**Cumulative Cost:** \$179,995

GMBU L-22-8-17**Wait on Completion****Date:** 5/1/2011

NDSI SS #1 at 6683. 4 Days Since Spud - Clean Mud Tanks - 1.24 yield, returned 29bbls to pit. - Pumped 416sks 50:50:2+3%KCL+.5%EC-1+.25#CF+.05#SF+.3SMS+FP-6L Mixed @ 14.4ppg W/ - Cement W/ 300sks PL11+3%KCL+5#CSE+.5#CF+2#KOL+.5sms+FP+SF Mixed @ 11ppg W/3.53 yield - Circulate Casing, rig up BJ - Run 159jts J-55 LTC 15.5# 5 1/2" Casing, Hang Mandrel W/ 75,000# Casing set @ 6669.29KB - Release Rig @ 3:30PM 4/30/11 Ryan Crum **Finalized**

Daily Cost: \$0

Cumulative Cost: \$296,475

Pertinent Files: Go to File List

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
Other: _____

2. Name of Operator
NEWFIELD EXPLORATION COMPANY

3. Address
1401 17TH ST. SUITE 1000 DENVER, CO 80202

3a. Phone No. (include area code)
(435) 646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 2007' FNL & 2000' FEL (SW/NE) SEC. 22, T8S, R17E (UTU-77233)

At top prod. interval reported below 2363' FNL & 1333' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233)

At total depth 2536' FNL & 985' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233)

14. Date Spudded
04/15/2011

15. Date T.D. Reached
04/30/2011

16. Date Completed 05/20/2011
☐ D & A ☒ Ready to Prod.

18. Total Depth: MD 6683'
TVD 6570'

19. Plug Back T.D.: MD 6645'
TVD 6533

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND

22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24#	0	360'		180 CLASS G			
7-7/8"	5-1/2" J-55	15.5#	0	6669'		300 PRIMLITE		49'	
						416 50/50 POZ			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT @ 6436'	TA @ 6269'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River	4532'	6517'	6511-6517'	.36"	18	
B)			4532-6290'	.34"	111	
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
4532-6517'	Frac w/ 192211#s 20/40 sand in 1377 bbls of Lightning 17 fluid in 5 stages

RECEIVED

JUN 15 2011

DIV. OF OIL, GAS & MINING

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
5/27/11	6/6/11	24	→	66	45	25			2-1/2" x 1-3/4" x 20' x 21' x 24' RHAC Pump
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

SOLD AND USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH GREEN RIVER	7267' 5412'	7338' 7030'		GARDEN GULCH MRK	4971'
				GARDEN GULCH 1	5163'
				GARDEN GULCH 2	5290'
				POINT 3	5619'
				X MRKR	5793'
				Y MRKR	5834'
				DOUGALS CREEK MRK	5996'
				BI-CARB	6282'
				B LIMESTONE MARK	6453'
				CASTLE PEAK	6721'
				BASAL CARBONATE	7067'
				WASATCH	7175'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling Daily Activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Jennifer Peatross

Title Production Technician

Signature

Date 06/07/2011

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 22 T8S, R17E
L-22-8-17**

Wellbore #1

Design: Actual

Standard Survey Report

09 May, 2011

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 22 T8S, R17E, SEC 22 T8S, R17E		
Site Position:		Northing:	7,208,900.00 ft
From:	Lat/Long	Easting:	2,062,000.00 ft
Position Uncertainty:	0.0 ft	Slot Radius:	"
		Latitude:	40° 6' 1.964 N
		Longitude:	109° 59' 34.084 W
		Grid Convergence:	0.97 °

Well	L-22-8-17, SHL LAT: 40° 06' 18.71, LONG: -109° 59' 24.97		
Well Position	+N/-S	0.0 ft	Northing:
	+E/-W	0.0 ft	Easting:
Position Uncertainty	0.0 ft	Wellhead Elevation:	5,136.0 ft
		Latitude:	40° 6' 18.710 N
		Longitude:	109° 59' 24.970 W
		Ground Level:	5,124.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/09/27	11.38	65.88	52,387

Design	Actual				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	117.76	

Survey Program	Date 2011/05/09				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
383.0	6,683.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
383.0	0.70	177.30	383.0	-2.3	0.1	1.2	0.18	0.18	0.00
414.0	0.80	156.20	414.0	-2.7	0.2	1.5	0.94	0.32	-68.06
445.0	1.10	150.10	445.0	-3.2	0.4	1.9	1.02	0.97	-19.68
475.0	1.50	156.60	475.0	-3.8	0.7	2.4	1.42	1.33	21.67
506.0	1.80	147.00	506.0	-4.6	1.2	3.2	1.31	0.97	-30.97
536.0	1.90	144.90	535.9	-5.4	1.7	4.0	0.40	0.33	-7.00
567.0	2.20	150.10	566.9	-6.3	2.3	5.0	1.14	0.97	16.77
597.0	2.80	150.70	596.9	-7.4	2.9	6.1	2.00	2.00	2.00
628.0	2.90	151.20	627.9	-8.8	3.7	7.4	0.33	0.32	1.61
659.0	2.80	149.40	658.8	-10.1	4.5	8.7	0.43	-0.32	-5.81
689.0	3.30	144.80	688.8	-11.5	5.3	10.1	1.85	1.67	-15.33
719.0	3.60	143.90	718.7	-12.9	6.4	11.7	1.02	1.00	-3.00

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
750.0	4.10	143.30	749.7	-14.6	7.6	13.5	1.62	1.61	-1.94
781.0	4.40	145.20	780.6	-16.5	9.0	15.6	1.07	0.97	6.13
812.0	4.70	145.20	811.5	-18.5	10.4	17.8	0.97	0.97	0.00
855.0	5.90	140.50	854.3	-21.6	12.8	21.4	2.97	2.79	-10.93
900.0	6.90	138.00	899.0	-25.4	16.1	26.1	2.31	2.22	-5.56
944.0	7.40	137.50	942.7	-29.5	19.7	31.2	1.15	1.14	-1.14
988.0	7.80	137.30	986.3	-33.8	23.7	36.7	0.91	0.91	-0.45
1,032.0	8.30	137.70	1,029.8	-38.3	27.8	42.5	1.14	1.14	0.91
1,076.0	8.80	135.50	1,073.4	-43.1	32.3	48.7	1.36	1.14	-5.00
1,120.0	9.20	134.80	1,116.8	-47.9	37.2	55.2	0.94	0.91	-1.59
1,164.0	9.40	131.10	1,160.2	-52.8	42.4	62.1	1.43	0.45	-8.41
1,208.0	10.20	129.80	1,203.6	-57.6	48.1	69.4	1.89	1.82	-2.95
1,252.0	10.80	128.80	1,246.9	-62.7	54.3	77.3	1.43	1.36	-2.27
1,296.0	11.40	126.90	1,290.0	-67.9	61.0	85.6	1.60	1.36	-4.32
1,340.0	11.30	123.50	1,333.2	-72.9	68.1	94.2	1.54	-0.23	-7.73
1,384.0	11.10	121.00	1,376.3	-77.5	75.3	102.7	1.19	-0.45	-5.68
1,428.0	11.20	117.10	1,419.5	-81.6	82.7	111.2	1.73	0.23	-8.86
1,472.0	11.70	116.30	1,462.6	-85.5	90.5	119.9	1.19	1.14	-1.82
1,516.0	11.90	114.50	1,505.7	-89.4	98.7	128.9	0.95	0.45	-4.09
1,560.0	11.90	115.10	1,548.8	-93.2	106.9	138.0	0.28	0.00	1.36
1,604.0	12.10	115.40	1,591.8	-97.1	115.2	147.1	0.48	0.45	0.68
1,648.0	12.20	114.50	1,634.8	-101.0	123.6	156.4	0.49	0.23	-2.05
1,692.0	12.50	114.10	1,677.8	-104.9	132.1	165.8	0.71	0.68	-0.91
1,736.0	12.30	114.80	1,720.8	-108.8	140.7	175.2	0.57	-0.45	1.59
1,780.0	12.60	113.90	1,763.7	-112.7	149.4	184.7	0.81	0.68	-2.05
1,824.0	12.80	113.40	1,806.7	-116.6	158.2	194.3	0.52	0.45	-1.14
1,868.0	12.70	114.10	1,849.6	-120.5	167.1	204.0	0.42	-0.23	1.59
1,912.0	12.80	113.40	1,892.5	-124.4	176.0	213.7	0.42	0.23	-1.59
1,956.0	13.00	111.30	1,935.4	-128.1	185.1	223.5	1.16	0.45	-4.77
2,000.0	12.70	111.60	1,978.3	-131.7	194.2	233.2	0.70	-0.68	0.68
2,044.0	13.00	114.30	2,021.2	-135.5	203.2	242.9	1.53	0.68	6.14
2,088.0	13.20	113.40	2,064.0	-139.5	212.3	252.9	0.65	0.45	-2.05
2,132.0	13.00	114.20	2,106.9	-143.6	221.5	262.8	0.61	-0.45	1.82
2,176.0	12.90	111.90	2,149.8	-147.4	230.5	272.7	1.19	-0.23	-5.23
2,220.0	12.40	112.40	2,192.7	-151.1	239.5	282.3	1.16	-1.14	1.14
2,264.0	12.20	113.40	2,235.7	-154.7	248.1	291.6	0.66	-0.45	2.27
2,308.0	11.90	111.90	2,278.7	-158.2	256.6	300.7	0.99	-0.68	-3.41
2,352.0	11.30	110.40	2,321.8	-161.4	264.8	309.5	1.53	-1.36	-3.41
2,396.0	10.80	110.10	2,365.0	-164.4	272.7	317.9	1.14	-1.14	-0.68
2,440.0	10.50	110.60	2,408.2	-167.2	280.4	326.0	0.71	-0.68	1.14
2,484.0	10.10	110.50	2,451.5	-170.0	287.7	333.8	0.91	-0.91	-0.23
2,528.0	10.30	109.70	2,494.8	-172.6	295.0	341.5	0.56	0.45	-1.82
2,572.0	10.80	109.10	2,538.1	-175.3	302.6	349.5	1.16	1.14	-1.36
2,615.0	11.30	109.70	2,580.3	-178.0	310.4	357.6	1.19	1.16	1.40
2,659.0	11.60	111.90	2,623.4	-181.1	318.6	366.3	1.20	0.68	5.00
2,703.0	11.50	112.30	2,666.5	-184.5	326.7	375.0	0.29	-0.23	0.91
2,747.0	11.30	113.40	2,709.7	-187.8	334.8	383.7	0.67	-0.45	2.50
2,792.0	11.10	115.10	2,753.8	-191.4	342.7	392.4	0.86	-0.44	3.78
2,836.0	11.30	119.30	2,797.0	-195.3	350.3	401.0	1.91	0.45	9.55
2,880.0	12.30	119.90	2,840.0	-199.8	358.1	410.0	2.29	2.27	1.36
2,924.0	12.50	123.00	2,883.0	-204.7	366.2	419.4	1.58	0.45	7.05
2,968.0	12.70	121.30	2,925.9	-209.8	374.3	429.0	0.96	0.45	-3.86
3,012.0	12.80	120.90	2,968.9	-214.8	382.6	438.7	0.30	0.23	-0.91
3,056.0	13.10	116.70	3,011.7	-219.6	391.3	448.5	2.24	0.68	-9.55

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,100.0	13.80	117.00	3,054.5	-224.2	400.4	458.7	1.60	1.59	0.68
3,144.0	14.00	117.20	3,097.2	-229.0	409.8	469.3	0.47	0.45	0.45
3,188.0	14.20	117.90	3,139.9	-234.0	419.3	480.0	0.60	0.45	1.59
3,231.0	13.70	116.30	3,181.7	-238.7	428.5	490.4	1.47	-1.16	-3.72
3,275.0	12.40	111.70	3,224.5	-242.7	437.6	500.3	3.78	-2.95	-10.45
3,319.0	11.70	110.40	3,267.5	-246.0	446.2	509.4	1.71	-1.59	-2.95
3,363.0	11.70	110.80	3,310.6	-249.2	454.5	518.3	0.18	0.00	0.91
3,407.0	11.70	111.50	3,353.7	-252.4	462.8	527.1	0.32	0.00	1.59
3,451.0	12.10	111.70	3,396.8	-255.7	471.3	536.2	0.91	0.91	0.45
3,495.0	11.90	112.90	3,439.8	-259.2	479.7	545.3	0.73	-0.45	2.73
3,539.0	12.40	113.10	3,482.8	-262.8	488.3	554.5	1.14	1.14	0.45
3,583.0	13.00	112.30	3,525.8	-266.6	497.2	564.1	1.42	1.36	-1.82
3,627.0	13.40	114.50	3,568.6	-270.6	506.4	574.1	1.46	0.91	5.00
3,671.0	12.50	114.80	3,611.5	-274.7	515.4	584.0	2.05	-2.05	0.68
3,715.0	12.10	115.60	3,654.5	-278.7	523.9	593.4	0.99	-0.91	1.82
3,759.0	12.40	117.80	3,697.5	-282.9	532.2	602.7	1.26	0.68	5.00
3,803.0	12.80	117.50	3,740.4	-287.3	540.7	612.3	0.92	0.91	-0.68
3,847.0	12.60	117.60	3,783.3	-291.8	549.3	622.0	0.46	-0.45	0.23
3,891.0	12.00	118.30	3,826.3	-296.2	557.6	631.3	1.41	-1.36	1.59
3,935.0	11.80	117.60	3,869.4	-300.4	565.6	640.4	0.56	-0.45	-1.59
3,979.0	11.60	115.10	3,912.5	-304.4	573.6	649.3	1.24	-0.45	-5.68
4,023.0	11.30	117.30	3,955.6	-308.2	581.4	658.1	1.20	-0.68	5.00
4,067.0	11.30	118.10	3,998.7	-312.3	589.0	666.7	0.36	0.00	1.82
4,112.0	11.60	120.60	4,042.8	-316.6	596.8	675.6	1.29	0.67	5.56
4,156.0	11.30	120.80	4,086.0	-321.1	604.3	684.3	0.69	-0.68	0.45
4,200.0	11.00	118.10	4,129.1	-325.3	611.7	692.8	1.37	-0.68	-6.14
4,244.0	10.40	117.20	4,172.4	-329.1	619.0	701.0	1.42	-1.36	-2.05
4,288.0	10.20	116.80	4,215.6	-332.6	626.0	708.9	0.48	-0.45	-0.91
4,332.0	9.90	119.10	4,259.0	-336.2	632.8	716.5	1.14	-0.68	5.23
4,376.0	10.00	121.00	4,302.3	-340.0	639.3	724.1	0.78	0.23	4.32
4,420.0	10.30	120.30	4,345.6	-344.0	646.0	731.9	0.74	0.68	-1.59
4,464.0	10.40	119.40	4,388.9	-347.9	652.9	739.8	0.43	0.23	-2.05
4,508.0	10.60	117.30	4,432.2	-351.7	659.9	747.8	0.98	0.45	-4.77
4,552.0	10.60	119.50	4,475.4	-355.6	667.0	755.9	0.92	0.00	5.00
4,596.0	10.50	119.50	4,518.7	-359.6	674.1	763.9	0.23	-0.23	0.00
4,640.0	10.80	117.80	4,561.9	-363.5	681.2	772.1	0.99	0.68	-3.86
4,684.0	10.50	116.60	4,605.2	-367.2	688.4	780.2	0.85	-0.68	-2.73
4,728.0	10.50	117.00	4,648.4	-370.8	695.6	788.2	0.17	0.00	0.91
4,772.0	10.30	115.70	4,691.7	-374.3	702.7	796.2	0.70	-0.45	-2.95
4,816.0	10.50	116.40	4,735.0	-377.8	709.8	804.1	0.54	0.45	1.59
4,860.0	10.10	116.70	4,778.3	-381.3	716.9	812.0	0.92	-0.91	0.68
4,904.0	9.60	118.80	4,821.6	-384.8	723.5	819.5	1.40	-1.14	4.77
4,948.0	9.00	123.80	4,865.0	-388.5	729.6	826.6	2.29	-1.36	11.36
4,992.0	9.10	124.20	4,908.5	-392.4	735.3	833.5	0.27	0.23	0.91
5,036.0	9.30	126.80	4,951.9	-396.5	741.1	840.4	1.05	0.45	5.91
5,080.0	9.90	125.80	4,995.3	-400.8	747.0	847.7	1.42	1.36	-2.27
5,124.0	9.70	123.70	5,038.7	-405.1	753.1	855.1	0.93	-0.45	-4.77
5,168.0	9.80	123.30	5,082.0	-409.2	759.3	862.5	0.27	0.23	-0.91
5,212.0	9.70	119.20	5,125.4	-413.0	765.7	870.0	1.59	-0.23	-9.32
5,256.0	9.70	118.20	5,168.8	-416.6	772.2	877.4	0.38	0.00	-2.27
5,300.0	10.20	114.40	5,212.1	-420.0	779.0	885.0	1.88	1.14	-8.64
5,344.0	10.70	110.90	5,255.4	-423.0	786.4	892.9	1.84	1.14	-7.95
5,388.0	10.70	109.40	5,298.6	-425.8	794.1	901.0	0.63	0.00	-3.41
5,432.0	10.80	112.90	5,341.8	-428.8	801.7	909.2	1.50	0.23	7.95

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,476.0	10.60	115.20	5,385.1	-432.1	809.2	917.3	1.07	-0.45	5.23
5,485.4	10.58	115.01	5,394.4	-432.9	810.7	919.0	0.44	-0.23	-2.03
L-22-8-17 TGT									
5,520.0	10.50	114.30	5,428.3	-435.5	816.5	925.4	0.44	-0.23	-2.05
5,564.0	10.40	115.50	5,471.6	-438.9	823.7	933.3	0.54	-0.23	2.73
5,608.0	10.30	114.80	5,514.9	-442.2	830.9	941.2	0.37	-0.23	-1.59
5,652.0	10.40	115.00	5,558.2	-445.6	838.1	949.1	0.24	0.23	0.45
5,696.0	10.50	113.60	5,601.4	-448.8	845.3	957.1	0.62	0.23	-3.18
5,740.0	10.70	114.00	5,644.7	-452.1	852.7	965.2	0.48	0.45	0.91
5,784.0	11.00	115.20	5,687.9	-455.6	860.3	973.4	0.85	0.68	2.73
5,828.0	10.80	117.40	5,731.1	-459.2	867.7	981.7	1.05	-0.45	5.00
5,872.0	10.40	115.60	5,774.4	-462.8	875.0	989.8	1.18	-0.91	-4.09
5,916.0	10.60	118.00	5,817.6	-466.5	882.1	997.9	1.09	0.45	5.45
5,960.0	10.70	117.20	5,860.9	-470.2	889.3	1,006.0	0.41	0.23	-1.82
6,004.0	11.40	118.60	5,904.1	-474.2	896.8	1,014.4	1.70	1.59	3.18
6,048.0	12.10	117.30	5,947.1	-478.4	904.7	1,023.4	1.70	1.59	-2.95
6,092.0	12.50	116.20	5,990.1	-482.6	913.1	1,032.7	1.05	0.91	-2.50
6,136.0	12.30	112.80	6,033.1	-486.5	921.7	1,042.2	1.72	-0.45	-7.73
6,180.0	11.20	113.50	6,076.2	-490.0	929.9	1,051.1	2.52	-2.50	1.59
6,224.0	11.30	113.40	6,119.3	-493.4	937.8	1,059.7	0.23	0.23	-0.23
6,268.0	11.40	114.60	6,162.5	-497.0	945.7	1,068.3	0.58	0.23	2.73
6,312.0	11.30	115.60	6,205.6	-500.6	953.5	1,077.0	0.50	-0.23	2.27
6,356.0	11.30	116.50	6,248.8	-504.4	961.3	1,085.6	0.40	0.00	2.05
6,400.0	11.00	115.20	6,291.9	-508.1	968.9	1,094.1	0.89	-0.68	-2.95
6,444.0	10.30	115.30	6,335.2	-511.6	976.3	1,102.2	1.59	-1.59	0.23
6,488.0	10.50	117.10	6,378.4	-515.1	983.4	1,110.1	0.87	0.45	4.09
6,532.0	10.40	115.60	6,421.7	-518.7	990.5	1,118.1	0.66	-0.23	-3.41
6,576.0	10.00	115.70	6,465.0	-522.0	997.6	1,125.9	0.91	-0.91	0.23
6,629.0	10.00	113.20	6,517.2	-525.8	1,005.9	1,135.1	0.82	0.00	-4.72
6,683.0	10.00	113.20	6,570.4	-529.5	1,014.6	1,144.4	0.00	0.00	0.00

Wellbore Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- hit/miss target									
- Shape									
L-22-8-17 TGT	0.00	0.00	5,400.0	-413.8	786.2	7,210,205.60	2,063,472.52	40° 6' 14.620 N	109° 59' 14.851 W
- actual wellpath misses by 31.6ft at 5485.4ft MD (5394.3 TVD, -432.9 N, 810.7 E)									
- Circle (radius 75.0)									

Checked By: _____ Approved By: _____ Date: _____

NEWFIELD





Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 SURVEY: Actual



Azimuths to True North
 Magnetic North: 11.38°

Magnetic Field
 Strength: 52387.2snT
 Dip Angle: 65.88°
 Date: 2010/09/27
 Model: IGRF2010



Design: Actual (L-22-8-17/Wellbore #1)



Created By: Sarah Webb Date: 14:31, May 09 2011
 THIS SURVEY IS CORRECT TO THE BEST OF MY
 KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA.

Daily Activity Report

Format For Sundry

GMBU L-22-8-17**2/1/2011 To 6/30/2011****GMBU L-22-8-17****Waiting on Cement****Date:** 4/18/2011

Ross #29 at 360. Days Since Spud - yield. Returned 6bbls to pit, bump plug to 475psi, BLM and State were notified of spud via email. - On 4/15/11 Ross #29 spud and drilled 360' of 12 1/4" hole, P/U and run 8 jts of 8 5/8" casing set - @ 357.62'KB. On 4/18/11 cement w/BJ w/180 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17

Daily Cost: \$0**Cumulative Cost:** \$58,320**GMBU L-22-8-17****Drill 7 7/8" hole with fresh water****Date:** 4/28/2011

NDSI SS #1 at 2538. 1 Days Since Spud - Pre spud meeting w/ crew and Payzone directional hands - MIRU SET ALL EQUIPMENT W/Liddell trucking - Gain circulation and tag @ 320' - Drill 7 7/8" hole F/320' - 2538', w/ 20 WOB, 160 RPM, 379 GPM, ROP 170 - Surface csg @ 1500 PSI - test good - P/U Security 7 7/8" PDC bit, Payzone directional tools, HWDP - R/U B&C quicktest Test Kelly,safty valve,choke manifold,Pipe and blind rams @ 2000 PSI

Daily Cost: \$0**Cumulative Cost:** \$94,693**GMBU L-22-8-17****Drill 7 7/8" hole with fresh water****Date:** 4/29/2011

NDSI SS #1 at 5838. 2 Days Since Spud - 2gal/min Flow @ 5398' - Drill 7 7/8" hole F/ 2538' to 3945, w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP - Rig Service, Grease Top Drive, Boom and Crown. - Drill 7 7/8" hole F/ 3945 to 5838', w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP

Daily Cost: \$0**Cumulative Cost:** \$121,507**GMBU L-22-8-17****Running casing****Date:** 4/30/2011

NDSI SS #1 at 6683. 3 Days Since Spud - Rig up B&C Quick Tests and Test 5 1/2" Casing Rams to 2,000PSI F/ 10min, tested good - Rig up PSI and run Wireline tools F/ TD to Surface - Laydown Drill Pipe and BHA - Pump 360bbls of Brine - Laydown Drill Pipe to 4,000' - Pump Sweep, Circulate Well F/ Laydown and Logs - Drill 7 7/8" hole F/ 5838' to 6683' TD, w/ 22,000 WOB, 160 RPM, 420 GPM, 130fph ROP - Rig up and Run 159jts J-55 LTC 15.5# 5 1/2" Casing

Daily Cost: \$0**Cumulative Cost:** \$179,995**GMBU L-22-8-17****Wait on Completion****Date:** 5/1/2011

NDSI SS #1 at 6683. 4 Days Since Spud - Clean Mud Tanks - 1.24 yield, returned 29bbls to pit. - Pumped 416sks 50:50:2+3%KCL+.5%EC-1+.25#CF+.05#SF+.3SMS+FP-6L Mixed @ 14.4ppg W/ - Cement W/ 300sks PL11+3%KCL+5#CSE+.5#CF+2#KOL+.5sms+FP+SF Mixed @ 11ppg W/3.53 yield - Circulate Casing, rig up BJ - Run 159jts J-55 LTC 15.5# 5 1/2" Casing, Hang Mandrel W/ 75,000# Casing set @ 6669.29KB - Release Rig @ 3:30PM 4/30/11 Ryan Crum **Finalized**

Daily Cost: \$0

Cumulative Cost: \$296,475

Pertinent Files: [Go to File List](#)

NEWFIELD PRODUCTION COMPANY

GEOLOGIC PROGNOSIS AND LOG DISTRIBUTION LIST

(4/15/2011)

WELL: GMB L-22-8-17

API Number: 4301350464

LOCATION: SL: 2007' FNL 2000' FEL (SWNE)
Section 22, T8S R17E

BHL: 2547' FNL 1004' FEL (SENE)
Section 22, T8S R17E
Duchesne County, Utah

ELEVATION: 5124' Ground
5136' KB

			ANTICIPATED		
TOPS:	MD	TVD	PAY SANDS:	MD	TVD
Uinta Formation	surface'	surface'	GB 2	4572'	4625'
Green River Formation	1795'	1775'	GB 4	4740'	4690'
Garden Gulch Member	4565'	4515'	GB 6	4796'	4745'
Point Three Marker	4853'	4800'	PB 7	Not Expected	Not Expected
'X' Marker	5086'	5030'	PB 8	Not Expected	Not Expected
'Y' Marker	5116'	5060'	PB 10	Not Expected	Not Expected
Douglas Creek Member	5253'	5195'	PB 11	5054'	5000'
Bi Carb	5546'	5485'	DS 1	Not Expected	Not Expected
B Limestone	5693'	5630'	DS 2	Not Expected	Not Expected
Castle Peak Limestone	6102'	6035'	DS 3	5213'	5155'
Basal Limestones	6517'	6445'	D 1	Not Expected	Not Expected
			D 2	5335'	5275'
TOTAL DEPTH:	6643'	6570'	D 3	Not Expected	Not Expected
			C-sd	5446'	5385'
			B 0.5	Not Expected	Not Expected
			B 1	Not Expected	Not Expected
			B 2	Not Expected	Not Expected
			A 0.5	Not Expected	Not Expected
			A 1	Not Expected	Not Expected
			A 3	5841'	5775'
			LODC	5958'	5890'
			CP 0.5	6120'	6055'
			CP 1	6161'	6095'
			CP 2	6201'	6135'
			CP 3	Not Expected	Not Expected
			CP 4	Not Expected	Not Expected
			CP 5	Not Expected	Not Expected

DRILLING:

Rig Supervisor: Alvin Nielsen (435) 823-7468 cellular
Rig Supervisor: Ray Herrera (435) 823-1990 cellular
Rig Supervisor: Jim Smith (435) 823- 2072 cellular
Rig Supervisor: Justin Crum (435) 823-6733 cellular
Rig Supervisor: Don Bastian (435) 823-6012 cellular
Rig Supervisor: Xabier Lasa (435) 823-6013 cellular
Rig Supervisor: Johnny Davis (435) 823-3610 cellular
Rig Supervisor: Jay Burton (435) 823-0736 cellular
Rig Supervisor: Ryan Crum (435) 823-0267 cellular
Field Engineer: Sean Stevens (435) 823-1162 cellular

REPORT WATER FLOWS TO UTAH DIVISION OF OIL, GAS AND MINING: (801) 538 5327

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other										5. Lease Serial No. UTU-77233	
b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr., Other: _____										6. If Indian, Allottee or Tribe Name	
2. Name of Operator NEWFIELD EXPLORATION COMPANY										7. Unit or CA Agreement Name and No. Greater Monument Butte	
3. Address 1401 17TH ST. SUITE 1000 DENVER, CO 80202										8. Lease Name and Well No. Greater Monument Butte L-22-8-17	
3a. Phone No. (include area code) (435) 646-3721										9. AFI Well No. 43-047-34290 013-504164	
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface 2007' FNL & 2000' FEL (SW/NE) SEC. 22, T8S, R17E (UTU-77233) At top prod. interval reported below 2363' FNL & 1333' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233) At total depth 2536' FNL & 985' FEL (SE/NE) SEC. 22, T8S, R17E (UTU-77233) <i>BH reviewed by HSM</i>										10. Field and Pool or Exploratory Monument Butte	
										11. Sec., T., R., M., on Block and Survey or Area SEC. 22, T8S, R17E	
										12. County or Parish DUCHESNE	
										13. State UT	
14. Date Spudded 04/15/2011										15. Date T.D. Reached 04/30/2011	
16. Date Completed 05/20/2011 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.										17. Elevations (DF, RKB, RT, GL)* 5124' GL 5136' KB	
18. Total Depth: MD 6683' TVD 6570'										19. Plug Back T.D.: MD 6645' TVD 6533	
20. Depth Bridge Plug Set: MD TVD											
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) DUAL IND GRD, SP, COMP. DENSITY, COMP. NEUTRON, GR, CALIPER, CMT BOND										22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)	
23. Casing and Liner Record (Report all strings set in well)											
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled		
12-1/4"	8-5/8" J-55	24#	0	360'		180 CLASS G					
7-7/8"	5-1/2" J-55	15.5#	0	6669'		300 PRIMLITE		49'			
						416 50/50 POZ					
24. Tubing Record											
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)			
2-7/8"	EOT@ 6436'	TA @ 6269'									
25. Producing Intervals											
Formation		Top	Bottom	Perforated Interval		Size	No. Holes	Perf. Status			
A) Green River		4532'	6517'	6511-6517'		.36"	18				
B)				4532-6290'		.34"	111				
C)											
D)											
27. Acid, Fracture, Treatment, Cement Squeeze, etc.											
Depth Interval		Amount and Type of Material									
4532-6517'		Frac w/ 192211#s 20/40 sand in 1377 bbls of Lightning 17 fluid in 5 stages									
RECEIVED											
JUN 15 2011											
DIV. OF OIL, GAS & MINING											
28. Production - Interval A											
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method		
5/27/11	6/6/11	24	→	66	45	25			2-1/2" x 1-3/4" x 20' x 21' x 24' RHAC Pump		
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status			
			→					PRODUCING			
28a. Production - Interval B											
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method		
			→								
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status			
			→								

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

SOLD AND USED FOR FUEL

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
WASATCH GREEN RIVER	7267'	7338'		GARDEN GULCH MRK GARDEN GULCH 1	4971' 5163'
	5412'	7030'		GARDEN GULCH 2 POINT 3	5290' 5619'
				X MRKR Y MRKR	5793' 5834'
				DOUGALS CREEK MRK BI-CARB	5996' 6282'
				B LIMESTONE MARK CASTLE PEAK	6453' 6721'
				BASAL CARBONATE WASATCH	7067' 7175'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling Daily Activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Jennifer PeatrossTitle Production TechnicianSignature Date 06/07/2011

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 22 T8S, R17E
L-22-8-17**

Wellbore #1

Design: Actual

Standard Survey Report

09 May, 2011

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	SECTION 22 T8S, R17E, SEC 22 T8S, R17E		
Site Position:		Northing:	7,208,900.00 ft
From:	Lat/Long	Easting:	2,062,000.00 ft
Position Uncertainty:	0.0 ft	Slot Radius:	"
		Latitude:	40° 6' 1.964 N
		Longitude:	109° 59' 34.084 W
		Grid Convergence:	0.97 °

Well	L-22-8-17, SHL LAT: 40° 06' 18.71, LONG: -109° 59' 24.97		
Well Position	+N/-S	0.0 ft	Northing:
	+E/-W	0.0 ft	Easting:
Position Uncertainty	0.0 ft	Wellhead Elevation:	5,136.0 ft
		Latitude:	40° 6' 18.710 N
		Longitude:	109° 59' 24.970 W
		Ground Level:	5,124.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2010/09/27	11.38	65.88	52,387

Design	Actual				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	117.76	

Survey Program	Date 2011/05/09				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
383.0	6,683.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard	

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
383.0	0.70	177.30	383.0	-2.3	0.1	1.2	0.18	0.18	0.00
414.0	0.80	156.20	414.0	-2.7	0.2	1.5	0.94	0.32	-68.06
445.0	1.10	150.10	445.0	-3.2	0.4	1.9	1.02	0.97	-19.68
475.0	1.50	156.60	475.0	-3.8	0.7	2.4	1.42	1.33	21.67
506.0	1.80	147.00	506.0	-4.6	1.2	3.2	1.31	0.97	-30.97
536.0	1.90	144.90	535.9	-5.4	1.7	4.0	0.40	0.33	-7.00
567.0	2.20	150.10	566.9	-6.3	2.3	5.0	1.14	0.97	16.77
597.0	2.80	150.70	596.9	-7.4	2.9	6.1	2.00	2.00	2.00
628.0	2.90	151.20	627.9	-8.8	3.7	7.4	0.33	0.32	1.61
659.0	2.80	149.40	658.8	-10.1	4.5	8.7	0.43	-0.32	-5.81
689.0	3.30	144.80	688.8	-11.5	5.3	10.1	1.85	1.67	-15.33
719.0	3.60	143.90	718.7	-12.9	6.4	11.7	1.02	1.00	-3.00

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
750.0	4.10	143.30	749.7	-14.6	7.6	13.5	1.62	1.61	-1.94
781.0	4.40	145.20	780.6	-16.5	9.0	15.6	1.07	0.97	6.13
812.0	4.70	145.20	811.5	-18.5	10.4	17.8	0.97	0.97	0.00
855.0	5.90	140.50	854.3	-21.6	12.8	21.4	2.97	2.79	-10.93
900.0	6.90	138.00	899.0	-25.4	16.1	26.1	2.31	2.22	-5.56
944.0	7.40	137.50	942.7	-29.5	19.7	31.2	1.15	1.14	-1.14
988.0	7.80	137.30	986.3	-33.8	23.7	36.7	0.91	0.91	-0.45
1,032.0	8.30	137.70	1,029.8	-38.3	27.8	42.5	1.14	1.14	0.91
1,076.0	8.80	135.50	1,073.4	-43.1	32.3	48.7	1.36	1.14	-5.00
1,120.0	9.20	134.80	1,116.8	-47.9	37.2	55.2	0.94	0.91	-1.59
1,164.0	9.40	131.10	1,160.2	-52.8	42.4	62.1	1.43	0.45	-8.41
1,208.0	10.20	129.80	1,203.6	-57.6	48.1	69.4	1.89	1.82	-2.95
1,252.0	10.80	128.80	1,246.9	-62.7	54.3	77.3	1.43	1.36	-2.27
1,296.0	11.40	126.90	1,290.0	-67.9	61.0	85.6	1.60	1.36	-4.32
1,340.0	11.30	123.50	1,333.2	-72.9	68.1	94.2	1.54	-0.23	-7.73
1,384.0	11.10	121.00	1,376.3	-77.5	75.3	102.7	1.19	-0.45	-5.68
1,428.0	11.20	117.10	1,419.5	-81.6	82.7	111.2	1.73	0.23	-8.86
1,472.0	11.70	116.30	1,462.6	-85.5	90.5	119.9	1.19	1.14	-1.82
1,516.0	11.90	114.50	1,505.7	-89.4	98.7	128.9	0.95	0.45	-4.09
1,560.0	11.90	115.10	1,548.8	-93.2	106.9	138.0	0.28	0.00	1.36
1,604.0	12.10	115.40	1,591.8	-97.1	115.2	147.1	0.48	0.45	0.68
1,648.0	12.20	114.50	1,634.8	-101.0	123.6	156.4	0.49	0.23	-2.05
1,692.0	12.50	114.10	1,677.8	-104.9	132.1	165.8	0.71	0.68	-0.91
1,736.0	12.30	114.80	1,720.8	-108.8	140.7	175.2	0.57	-0.45	1.59
1,780.0	12.60	113.90	1,763.7	-112.7	149.4	184.7	0.81	0.68	-2.05
1,824.0	12.80	113.40	1,806.7	-116.6	158.2	194.3	0.52	0.45	-1.14
1,868.0	12.70	114.10	1,849.6	-120.5	167.1	204.0	0.42	-0.23	1.59
1,912.0	12.80	113.40	1,892.5	-124.4	176.0	213.7	0.42	0.23	-1.59
1,956.0	13.00	111.30	1,935.4	-128.1	185.1	223.5	1.16	0.45	-4.77
2,000.0	12.70	111.60	1,978.3	-131.7	194.2	233.2	0.70	-0.68	0.68
2,044.0	13.00	114.30	2,021.2	-135.5	203.2	242.9	1.53	0.68	6.14
2,088.0	13.20	113.40	2,064.0	-139.5	212.3	252.9	0.65	0.45	-2.05
2,132.0	13.00	114.20	2,106.9	-143.6	221.5	262.8	0.61	-0.45	1.82
2,176.0	12.90	111.90	2,149.8	-147.4	230.5	272.7	1.19	-0.23	-5.23
2,220.0	12.40	112.40	2,192.7	-151.1	239.5	282.3	1.16	-1.14	1.14
2,264.0	12.20	113.40	2,235.7	-154.7	248.1	291.6	0.66	-0.45	2.27
2,308.0	11.90	111.90	2,278.7	-158.2	256.6	300.7	0.99	-0.68	-3.41
2,352.0	11.30	110.40	2,321.8	-161.4	264.8	309.5	1.53	-1.36	-3.41
2,396.0	10.80	110.10	2,365.0	-164.4	272.7	317.9	1.14	-1.14	-0.68
2,440.0	10.50	110.60	2,408.2	-167.2	280.4	326.0	0.71	-0.68	1.14
2,484.0	10.10	110.50	2,451.5	-170.0	287.7	333.8	0.91	-0.91	-0.23
2,528.0	10.30	109.70	2,494.8	-172.6	295.0	341.5	0.56	0.45	-1.82
2,572.0	10.80	109.10	2,538.1	-175.3	302.6	349.5	1.16	1.14	-1.36
2,615.0	11.30	109.70	2,580.3	-178.0	310.4	357.6	1.19	1.16	1.40
2,659.0	11.60	111.90	2,623.4	-181.1	318.6	366.3	1.20	0.68	5.00
2,703.0	11.50	112.30	2,666.5	-184.5	326.7	375.0	0.29	-0.23	0.91
2,747.0	11.30	113.40	2,709.7	-187.8	334.8	383.7	0.67	-0.45	2.50
2,792.0	11.10	115.10	2,753.8	-191.4	342.7	392.4	0.86	-0.44	3.78
2,836.0	11.30	119.30	2,797.0	-195.3	350.3	401.0	1.91	0.45	9.55
2,880.0	12.30	119.90	2,840.0	-199.8	358.1	410.0	2.29	2.27	1.36
2,924.0	12.50	123.00	2,883.0	-204.7	366.2	419.4	1.58	0.45	7.05
2,968.0	12.70	121.30	2,925.9	-209.8	374.3	429.0	0.96	0.45	-3.86
3,012.0	12.80	120.90	2,968.9	-214.8	382.6	438.7	0.30	0.23	-0.91
3,056.0	13.10	116.70	3,011.7	-219.6	391.3	448.5	2.24	0.68	-9.55

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,100.0	13.80	117.00	3,054.5	-224.2	400.4	458.7	1.60	1.59	0.68
3,144.0	14.00	117.20	3,097.2	-229.0	409.8	469.3	0.47	0.45	0.45
3,188.0	14.20	117.90	3,139.9	-234.0	419.3	480.0	0.60	0.45	1.59
3,231.0	13.70	116.30	3,181.7	-238.7	428.5	490.4	1.47	-1.16	-3.72
3,275.0	12.40	111.70	3,224.5	-242.7	437.6	500.3	3.78	-2.95	-10.45
3,319.0	11.70	110.40	3,267.5	-246.0	446.2	509.4	1.71	-1.59	-2.95
3,363.0	11.70	110.80	3,310.6	-249.2	454.5	518.3	0.18	0.00	0.91
3,407.0	11.70	111.50	3,353.7	-252.4	462.8	527.1	0.32	0.00	1.59
3,451.0	12.10	111.70	3,396.8	-255.7	471.3	536.2	0.91	0.91	0.45
3,495.0	11.90	112.90	3,439.8	-259.2	479.7	545.3	0.73	-0.45	2.73
3,539.0	12.40	113.10	3,482.8	-262.8	488.3	554.5	1.14	1.14	0.45
3,583.0	13.00	112.30	3,525.8	-266.6	497.2	564.1	1.42	1.36	-1.82
3,627.0	13.40	114.50	3,568.6	-270.6	506.4	574.1	1.46	0.91	5.00
3,671.0	12.50	114.80	3,611.5	-274.7	515.4	584.0	2.05	-2.05	0.68
3,715.0	12.10	115.60	3,654.5	-278.7	523.9	593.4	0.99	-0.91	1.82
3,759.0	12.40	117.80	3,697.5	-282.9	532.2	602.7	1.26	0.68	5.00
3,803.0	12.80	117.50	3,740.4	-287.3	540.7	612.3	0.92	0.91	-0.68
3,847.0	12.60	117.60	3,783.3	-291.8	549.3	622.0	0.46	-0.45	0.23
3,891.0	12.00	118.30	3,826.3	-296.2	557.6	631.3	1.41	-1.36	1.59
3,935.0	11.80	117.60	3,869.4	-300.4	565.6	640.4	0.56	-0.45	-1.59
3,979.0	11.60	115.10	3,912.5	-304.4	573.6	649.3	1.24	-0.45	-5.68
4,023.0	11.30	117.30	3,955.6	-308.2	581.4	658.1	1.20	-0.68	5.00
4,067.0	11.30	118.10	3,998.7	-312.3	589.0	666.7	0.36	0.00	1.82
4,112.0	11.60	120.60	4,042.8	-316.6	596.8	675.6	1.29	0.67	5.56
4,156.0	11.30	120.80	4,086.0	-321.1	604.3	684.3	0.69	-0.68	0.45
4,200.0	11.00	118.10	4,129.1	-325.3	611.7	692.8	1.37	-0.68	-6.14
4,244.0	10.40	117.20	4,172.4	-329.1	619.0	701.0	1.42	-1.36	-2.05
4,288.0	10.20	116.80	4,215.6	-332.6	626.0	708.9	0.48	-0.45	-0.91
4,332.0	9.90	119.10	4,259.0	-336.2	632.8	716.5	1.14	-0.68	5.23
4,376.0	10.00	121.00	4,302.3	-340.0	639.3	724.1	0.78	0.23	4.32
4,420.0	10.30	120.30	4,345.6	-344.0	646.0	731.9	0.74	0.68	-1.59
4,464.0	10.40	119.40	4,388.9	-347.9	652.9	739.8	0.43	0.23	-2.05
4,508.0	10.60	117.30	4,432.2	-351.7	659.9	747.8	0.98	0.45	-4.77
4,552.0	10.60	119.50	4,475.4	-355.6	667.0	755.9	0.92	0.00	5.00
4,596.0	10.50	119.50	4,518.7	-359.6	674.1	763.9	0.23	-0.23	0.00
4,640.0	10.80	117.80	4,561.9	-363.5	681.2	772.1	0.99	0.68	-3.86
4,684.0	10.50	116.60	4,605.2	-367.2	688.4	780.2	0.85	-0.68	-2.73
4,728.0	10.50	117.00	4,648.4	-370.8	695.6	788.2	0.17	0.00	0.91
4,772.0	10.30	115.70	4,691.7	-374.3	702.7	796.2	0.70	-0.45	-2.95
4,816.0	10.50	116.40	4,735.0	-377.8	709.8	804.1	0.54	0.45	1.59
4,860.0	10.10	116.70	4,778.3	-381.3	716.9	812.0	0.92	-0.91	0.68
4,904.0	9.60	118.80	4,821.6	-384.8	723.5	819.5	1.40	-1.14	4.77
4,948.0	9.00	123.80	4,865.0	-388.5	729.6	826.6	2.29	-1.36	11.36
4,992.0	9.10	124.20	4,908.5	-392.4	735.3	833.5	0.27	0.23	0.91
5,036.0	9.30	126.80	4,951.9	-396.5	741.1	840.4	1.05	0.45	5.91
5,080.0	9.90	125.80	4,995.3	-400.8	747.0	847.7	1.42	1.36	-2.27
5,124.0	9.70	123.70	5,038.7	-405.1	753.1	855.1	0.93	-0.45	-4.77
5,168.0	9.80	123.30	5,082.0	-409.2	759.3	862.5	0.27	0.23	-0.91
5,212.0	9.70	119.20	5,125.4	-413.0	765.7	870.0	1.59	-0.23	-9.32
5,256.0	9.70	118.20	5,168.8	-416.6	772.2	877.4	0.38	0.00	-2.27
5,300.0	10.20	114.40	5,212.1	-420.0	779.0	885.0	1.88	1.14	-8.64
5,344.0	10.70	110.90	5,255.4	-423.0	786.4	892.9	1.84	1.14	-7.95
5,388.0	10.70	109.40	5,298.6	-425.8	794.1	901.0	0.63	0.00	-3.41
5,432.0	10.80	112.90	5,341.8	-428.8	801.7	909.2	1.50	0.23	7.95

Company: NEWFIELD EXPLORATION
 Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 Design: Actual

Local Co-ordinate Reference: Well L-22-8-17
 TVD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 MD Reference: L-22-8-17 @ 5136.0ft (Original Well Elev)
 North Reference: True
 Survey Calculation Method: Minimum Curvature
 Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,476.0	10.60	115.20	5,385.1	-432.1	809.2	917.3	1.07	-0.45	5.23
5,485.4	10.58	115.01	5,394.4	-432.9	810.7	919.0	0.44	-0.23	-2.03
L-22-8-17 TGT									
5,520.0	10.50	114.30	5,428.3	-435.5	816.5	925.4	0.44	-0.23	-2.05
5,564.0	10.40	115.50	5,471.6	-438.9	823.7	933.3	0.54	-0.23	2.73
5,608.0	10.30	114.80	5,514.9	-442.2	830.9	941.2	0.37	-0.23	-1.59
5,652.0	10.40	115.00	5,558.2	-445.6	838.1	949.1	0.24	0.23	0.45
5,696.0	10.50	113.60	5,601.4	-448.8	845.3	957.1	0.62	0.23	-3.18
5,740.0	10.70	114.00	5,644.7	-452.1	852.7	965.2	0.48	0.45	0.91
5,784.0	11.00	115.20	5,687.9	-455.6	860.3	973.4	0.85	0.68	2.73
5,828.0	10.80	117.40	5,731.1	-459.2	867.7	981.7	1.05	-0.45	5.00
5,872.0	10.40	115.60	5,774.4	-462.8	875.0	989.8	1.18	-0.91	-4.09
5,916.0	10.60	118.00	5,817.6	-466.5	882.1	997.9	1.09	0.45	5.45
5,960.0	10.70	117.20	5,860.9	-470.2	889.3	1,006.0	0.41	0.23	-1.82
6,004.0	11.40	118.60	5,904.1	-474.2	896.8	1,014.4	1.70	1.59	3.18
6,048.0	12.10	117.30	5,947.1	-478.4	904.7	1,023.4	1.70	1.59	-2.95
6,092.0	12.50	116.20	5,990.1	-482.6	913.1	1,032.7	1.05	0.91	-2.50
6,136.0	12.30	112.80	6,033.1	-486.5	921.7	1,042.2	1.72	-0.45	-7.73
6,180.0	11.20	113.50	6,076.2	-490.0	929.9	1,051.1	2.52	-2.50	1.59
6,224.0	11.30	113.40	6,119.3	-493.4	937.8	1,059.7	0.23	0.23	-0.23
6,268.0	11.40	114.60	6,162.5	-497.0	945.7	1,068.3	0.58	0.23	2.73
6,312.0	11.30	115.60	6,205.6	-500.6	953.5	1,077.0	0.50	-0.23	2.27
6,356.0	11.30	116.50	6,248.8	-504.4	961.3	1,085.6	0.40	0.00	2.05
6,400.0	11.00	115.20	6,291.9	-508.1	968.9	1,094.1	0.89	-0.68	-2.95
6,444.0	10.30	115.30	6,335.2	-511.6	976.3	1,102.2	1.59	-1.59	0.23
6,488.0	10.50	117.10	6,378.4	-515.1	983.4	1,110.1	0.87	0.45	4.09
6,532.0	10.40	115.60	6,421.7	-518.7	990.5	1,118.1	0.66	-0.23	-3.41
6,576.0	10.00	115.70	6,465.0	-522.0	997.6	1,125.9	0.91	-0.91	0.23
6,629.0	10.00	113.20	6,517.2	-525.8	1,005.9	1,135.1	0.82	0.00	-4.72
6,683.0	10.00	113.20	6,570.4	-529.5	1,014.6	1,144.4	0.00	0.00	0.00

Wellbore Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- hit/miss target									
- Shape									
L-22-8-17 TGT	0.00	0.00	5,400.0	-413.8	786.2	7,210,205.60	2,063,472.52	40° 6' 14.620 N	109° 59' 14.851 W
- actual wellpath misses by 31.6ft at 5485.4ft MD (5394.3 TVD, -432.9 N, 810.7 E)									
- Circle (radius 75.0)									

Checked By: _____ Approved By: _____ Date: _____

NEWFIELD





Project: USGS Myton SW (UT)
 Site: SECTION 22 T8S, R17E
 Well: L-22-8-17
 Wellbore: Wellbore #1
 SURVEY: Actual



Azimuths to True North
 Magnetic North: 11.38°

Magnetic Field
 Strength: 52387.2snT
 Dip Angle: 65.88°
 Date: 2010/09/27
 Model: IGRF2010



Design: Actual (L-22-8-17/Wellbore #1)



Created By: Sarah Webb Date: 14:31, May 09 2011
 THIS SURVEY IS CORRECT TO THE BEST OF MY
 KNOWLEDGE AND IS SUPPORTED BY ACTUAL FIELD DATA.

Daily Activity Report

Format For Sundry

GMBU L-22-8-17**2/1/2011 To 6/30/2011****GMBU L-22-8-17****Waiting on Cement****Date:** 4/18/2011

Ross #29 at 360. Days Since Spud - yield. Returned 6bbls to pit, bump plug to 475psi, BLM and State were notified of spud via email. - On 4/15/11 Ross #29 spud and drilled 360' of 12 1/4" hole, P/U and run 8 jts of 8 5/8" casing set - @ 357.62'KB. On 4/18/11 cement w/BJ w/180 sks of class G+2%kcl+.25#CF mixed @ 15.8ppg and 1.17

Daily Cost: \$0**Cumulative Cost:** \$58,320**GMBU L-22-8-17****Drill 7 7/8" hole with fresh water****Date:** 4/28/2011

NDSI SS #1 at 2538. 1 Days Since Spud - Pre spud meeting w/ crew and Payzone directional hands - MIRU SET ALL EQUIPMENT W/Liddell trucking - Gain circulation and tag @ 320' - Drill 7 7/8" hole F/320' - 2538', w/ 20 WOB, 160 RPM, 379 GPM, ROP 170 - Surface csg @ 1500 PSI - test good - P/U Security 7 7/8" PDC bit, Payzone directional tools, HWDP - R/U B&C quicktest Test Kelly,safty valve,choke manifold,Pipe and blind rams @ 2000 PSI

Daily Cost: \$0**Cumulative Cost:** \$94,693**GMBU L-22-8-17****Drill 7 7/8" hole with fresh water****Date:** 4/29/2011

NDSI SS #1 at 5838. 2 Days Since Spud - 2gal/min Flow @ 5398' - Drill 7 7/8" hole F/ 2538' to 3945, w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP - Rig Service, Grease Top Drive, Boom and Crown. - Drill 7 7/8" hole F/ 3945 to 5838', w/ 20,000 WOB, 160 RPM, 420 GPM, 140fph ROP

Daily Cost: \$0**Cumulative Cost:** \$121,507**GMBU L-22-8-17****Running casing****Date:** 4/30/2011

NDSI SS #1 at 6683. 3 Days Since Spud - Rig up B&C Quick Tests and Test 5 1/2" Casing Rams to 2,000PSI F/ 10min, tested good - Rig up PSI and run Wireline tools F/ TD to Surface - Laydown Drill Pipe and BHA - Pump 360bbls of Brine - Laydown Drill Pipe to 4,000' - Pump Sweep, Circulate Well F/ Laydown and Logs - Drill 7 7/8" hole F/ 5838' to 6683' TD, w/ 22,000 WOB, 160 RPM, 420 GPM, 130fph ROP - Rig up and Run 159jts J-55 LTC 15.5# 5 1/2" Casing

Daily Cost: \$0**Cumulative Cost:** \$179,995**GMBU L-22-8-17****Wait on Completion****Date:** 5/1/2011

NDSI SS #1 at 6683. 4 Days Since Spud - Clean Mud Tanks - 1.24 yield, returned 29bbls to pit. - Pumped 416sks 50:50:2+3%KCL+.5%EC-1+.25#CF+.05#SF+.3SMS+FP-6L Mixed @ 14.4ppg W/ - Cement W/ 300sks PL11+3%KCL+5#CSE+.5#CF+2#KOL+.5sms+FP+SF Mixed @ 11ppg W/3.53 yield - Circulate Casing, rig up BJ - Run 159jts J-55 LTC 15.5# 5 1/2" Casing, Hang Mandrel W/ 75,000# Casing set @ 6669.29KB - Release Rig @ 3:30PM 4/30/11 Ryan Crum **Finalized**

Daily Cost: \$0

Cumulative Cost: \$296,475

Pertinent Files: [Go to File List](#)

NEWFIELD PRODUCTION COMPANY

GEOLOGIC PROGNOSIS AND LOG DISTRIBUTION LIST

(4/15/2011)

WELL: GMB L-22-8-17

API Number: 4301350464

LOCATION: SL: 2007' FNL 2000' FEL (SWNE)
Section 22, T8S R17E

BHL: 2547' FNL 1004' FEL (SENE)
Section 22, T8S R17E
Duchesne County, Utah

ELEVATION: 5124' Ground
5136' KB

			ANTICIPATED		
TOPS:	MD	TVD	PAY SANDS:	MD	TVD
Uinta Formation	surface'	surface'	GB 2	4572'	4625'
Green River Formation	1795'	1775'	GB 4	4740'	4690'
Garden Gulch Member	4565'	4515'	GB 6	4796'	4745'
Point Three Marker	4853'	4800'	PB 7	Not Expected	Not Expected
'X' Marker	5086'	5030'	PB 8	Not Expected	Not Expected
'Y' Marker	5116'	5060'	PB 10	Not Expected	Not Expected
Douglas Creek Member	5253'	5195'	PB 11	5054'	5000'
Bi Carb	5546'	5485'	DS 1	Not Expected	Not Expected
B Limestone	5693'	5630'	DS 2	Not Expected	Not Expected
Castle Peak Limestone	6102'	6035'	DS 3	5213'	5155'
Basal Limestones	6517'	6445'	D 1	Not Expected	Not Expected
			D 2	5335'	5275'
TOTAL DEPTH:	6643'	6570'	D 3	Not Expected	Not Expected
			C-sd	5446'	5385'
			B 0.5	Not Expected	Not Expected
			B 1	Not Expected	Not Expected
			B 2	Not Expected	Not Expected
			A 0.5	Not Expected	Not Expected
			A 1	Not Expected	Not Expected
			A 3	5841'	5775'
			LODC	5958'	5890'
			CP 0.5	6120'	6055'
			CP 1	6161'	6095'
			CP 2	6201'	6135'
			CP 3	Not Expected	Not Expected
			CP 4	Not Expected	Not Expected
			CP 5	Not Expected	Not Expected

DRILLING:

Rig Supervisor: Alvin Nielsen (435) 823-7468 cellular
Rig Supervisor: Ray Herrera (435) 823-1990 cellular
Rig Supervisor: Jim Smith (435) 823- 2072 cellular
Rig Supervisor: Justin Crum (435) 823-6733 cellular
Rig Supervisor: Don Bastian (435) 823-6012 cellular
Rig Supervisor: Xabier Lasa (435) 823-6013 cellular
Rig Supervisor: Johnny Davis (435) 823-3610 cellular
Rig Supervisor: Jay Burton (435) 823-0736 cellular
Rig Supervisor: Ryan Crum (435) 823-0267 cellular
Field Engineer: Sean Stevens (435) 823-1162 cellular

REPORT WATER FLOWS TO UTAH DIVISION OF OIL, GAS AND MINING: (801) 538 5327